

897 VIA LATA, SUITE N • COLTON, CA 92324 • (909) 370-0474 • (909) 370-0481 • FAX (909) 370-3156

Report of Soil Infiltration Tests Planned WQMP-BMP Storm Water Infiltration Retention Basins

Planned Truck and Trailer Facility Waalew Road. Apple Valley, California APN: 0440-014-11

Project No. 24019-BMP

May 14, 2024

Prepared for:

Weka, Inc. 236 W. Orange Show Road, Suite 114 San Bernardino, California 92408

> soilssouthwest@aol.com Established 1984

897 VIA LATA, SUITE N • COLTON, CA 92324 • (909) 370-0474 • (909) 370-0481 • FAX (909) 370-3156

May 14, 2024

Project No. 24019-BMP

Weka, Inc. 236 W. Orange Show Road, Suite 114 San Bernardino, California 92408

Attention:

Mr. Jared Himie

Subject:

Report of Soil Infiltration Tests

Planned WQMP-BMP Storm water Infiltration Retention Basins

Planned Truck and Trailer Facility Waalew Road. Apple Valley, California

APN: 0440-014-11

Reference:

1. Site Plan by Bonadiman & Associates

2. Riverside County Low Impact Development BMP Design Handbook &

San Bernardino County Technical Guidance Document for Water Quality Management

Plans Handbook

Gentlemen:

Presented herewith are the results of soils infiltration testing for the proposed WQMP-BMP stormwater Infiltration Basin design planned for the proposed site improvements to the existing Horsepower Ranch maintenance and equipment yard facility.

In general, the WQMP-BMP evaluations consisted of three (3) soil infiltration test borings, P-1, P-2, and P-3, within the general test locations as described in the development plan supplied (advanced to approximately 5 feet below the existing grade surface, respectively. The deeper boring evaluation was advanced to about 15 feet below grade to identify presence or absence of shallow-depth groundwater and shallow-depth impermeable layer, if any. Subsequent soils infiltration testing is performed using the standardized "falling-head" test methods, with the observed soil percolation rate being converted to infiltration rates using Porchet Method as per the guidelines of the Table 1, Infiltration Basin Option 2 method as described in the Appendix A of the Riverside County-Low Impact Development (LID) BMP design Handbook and as per the Appendix VII, Section VII.3.8.2: Infiltration Rate Evaluation Protocols as described in the San Bernardino County Technical Guidance Document for Water Quality Management Plans Handbook. Approximate test locations are shown on the attached Plate 1.

The soils encountered consist, in general, of upper 5 feet of consists of dry to damp slightly silty sands and silty sands with some damp to moist clayey sands (P-2) with occasional pebbles and scattered rock fragments to the proposed infiltration design system bottom of 5 feet below existing grade surface. For the exploratory deep boring (B-1), the soils primarily consist of upper 5 feet of fine to medium dry sands with some silts and pebbles overlying damp, slightly clayey fine to medium lumpy sand with pebbles and occasional rock fragments overlying dry fine to medium silty lumpy sands with pebbles, rock fragments, and scattered rock ½"-1" to the maximum depth of 15 feet explored. Test exploration logs are described in the Log of Borings P-1, P-2, P-3, and B-1, attached. No shallow-depth groundwater or layers considered impermeable to water was encountered.

Based on the testing completed, it is our opinion that the observed infiltration rates are 1.21 in/hr 0.00 inch/hr., and 0.67 inch/hr. for the test locations P-1, P-2, and P-3 respectively as described in Table II, Section 3.0 of this report. Considering the presence of lumpy damp to moist clayey sands within the tested depth for infiltration test borings, P-2 and P-3, infiltration tests results are low. Based on more favorable soils below the test depth (B-1@ 15 feet), it is our opinion that deeper testing and/or deeper infiltration design system may be considered.

For design an appropriate safety factor to the observed rate should be considered as selected by the project design engineer.

No 31708

Exp. 12-31-24

We offer no other warranty express or implied.

Respectfully submitted, Soils Southwest, Ing.

Moloy Gupta, RCE 3170

John Flippin, Project Supervisor

1.0 EXCAVATED TEST EXPLORATIONS

BMP soil percolation testing is performed at about 5 feet below grade for the test locations P-1 and P-2 respectively. An additional test boring (B-1) advanced to approximately 15 feet below grade surface is included primarily to identify presence or absence of groundwater and shallow depth bedrock, if any. The test explorations described are made using an 8-inch diameter hollow-stem auger drill rig for the test locations as shown on accompanying Plate 1. Water used during infiltration percolation testing is supplied by using a portable water jugs.

2.0 METHODOLOGY AND TEST PROCEDURES:

Following test boring completion, each of the test holes were fitted with perforated pvc pipes, underlain by 2-inch crushed rock at the bottoms to minimize potentials for scouring and caving. As per the handbook, for testing and to establish test intervals, each test hole was initially filled with 24-inch of water supplied as described.

During initial testing, since 6-inch or more water did not seep away in 25 minutes or less, subsequent percolation testing was performed at 30-minute time intervals for minimum six (6 hours, or until the soil percolation rates became relatively consistent for test borings, P-2 and P-3. For P-1since 6-inch or more water seeped away in 25 minutes or less, subsequent percolation testing was performed at 10-minute time intervals for minimum one (1) hour, or until the soil percolation rates became relatively consistent for test boringsActual testing included water placement at about 3 feet below the existing grade surface (inlet depth) or 24 inches above proposed infiltration chamber bottoms.

The final 10 and 30-minute recorded percolation test data were converted to an Infiltration Rate (It) in inches per hour using the "Porchet Method" equation as described in the Reference 2, Riverside County Low Impact Development BMP Design Handbook and San Bernardino County Technical Guidance Document for Water Quality Management Plans Handbook. The logs of soil percolation rates, along with the log for the deep test exploration and necessary calculations, are attached.

3.0 INFILTRATION TEST RESULTS

Based on the testing completed at the test locations and to the test depth described, it is our opinion that the observed soil *infiltration* rates are 1.21 in/hr 0.00 inch/hr. and 0.67 inch/hr. for the test locations P-1, P-2, and P-3 respectively. Calculations to convert the standardized "falling head" percolation rates to "infiltration" rates were in accordance with the Section 2.3 of the referenced County Handbooks are described in the following Table I and II. It is suggested that in design, use of an appropriate safety factor should be used to the observed rates as selected by the design engineer.

3.1. Conversion Summary and Calculations

TABLE I

Based on the testing completed, the following describes the observed field percolation rates for WQMP-BMP converted to soils design infiltration rate as per the referenced design handbooks. Actual field test data are attached.

Infiltration Rate for BMP Design

minication reaction beautiful										
Test Date &	Relative	Test	Observed Soil	Design <u>Infiltration</u> Rates						
Test No.	Site Location	Depth (ft.)	Percolation Rates	following Conversion of Soil						
(5-10-2024)		Below	(inch/hour.)	Percolation Rates						
		Grade		using Porchet Method						
				(with no Factor of Safety)						
P-1	North	5	2.5	1.21						
P-2	Center	5	0.0	0.00						
P-3	South	5	4.0	0.67						

TABLE II

Conversion Table (Porchet Method)

Test No.	Depth Test (inches)	Time Interval	Initial Depth (inch)	Final Depth (inch)	Initial Water Height (inch)	Final Water Height (inch)	Change in Height/ Time	Average Head Height/Time
	Dτ	Δ _{T (Min)}	D _O (in)	D _{f (in)}	H _o =D _t -D _o	H _f =D _t -D _f	ΔH= H _f -H _O	H _{avg} = (H _{o+} H _f)/2
P-1	60	10	36	38.5	24.0	21.5	2.5	22.75
P-2	60	30	36	36.0	24.0	24.0	0.0	24.0
P-3	60	30	36	40.0	24.0	20.0	4.0	22.0

	Observed Infiltration Rate (lt)=ΔH60r/Δt(r+2Havg)							
	Α	В	C (Factor of Safety not included)					
Test No.	ΔH60r	Δt(r+2Havg)	A/B=in/hr					
P-1	600	495	1.21					
P-2	0	1560	0.00					
P-3	960	1440	0.67					

In design, use of an appropriate safety factor should be considered to account for long-term saturation, inconsistencies in subsoil conditions, along with the potential for silting of percolating soils.

The infiltration rates described are based on the in-situ testing completed at the locations as suggested by the project civil engineer. In the event the test locations and the test depths described vary considerably supplemental soils infiltration testing may be warranted.

It should be noted that over prolong use and lack of maintenance the detention/infiltration basins or deep chambers constructed based on the suggested design rate may experience much lower infiltration rates due to the accumulation of silts, fines, soils, and others. Regular maintenance of the chambers in the form of removal of debris, oil and fines are strongly recommended. A maintenance record of such is suggested for future use, if any.

Suggested Requirements for Standard Stormwater BMP Installation

The invert of stormwater infiltration should be set at least 10 feet above the groundwater elevation and should not be placed on steep slopes to create conditions for slopes instability.

When adequately installed, it is our opinion that the Stormwater infiltration systems installed should not increase the potentials for static or seismic settlement of structures.

Stormwater infiltration installed should not place an increased surcharge on structures or foundations on or its adjacent. The pore water pressure should not increase the soils retained by retaining structures.

The invert of stormwater infiltration should be set back at least 15 feet and outside a 1:1 plan drawn up from the bottom of adjacent foundations.

Stormwater infiltration should not be located near utility lines where the introduction of stormwater could cause damage to utilities or settlement of trench backfill.

Stormwater infiltration systems should not be allowed within 100 feet of any potable groundwater production well.

Once installed, regular maintenance of the detention systems is recommended.

Stormwater infiltration shall not be located near utility lines where the introduction of stormwater could cause damage to utilities or settlement of trench backfill.

Stormwater infiltration is not allowed within 100 feet of any potable groundwater production well.

Once installed, regular maintenance of the installed systems should be considered.

LOG OF TEST BORINGS

PERCOLATION TEST DATA


And

LABORATORY ANALYSES

PLOT PLAN AND TEST LOCATIONS Planned Truck and Trailer Facility Waalew Road, Apple Valley, California APN: 0440-014-11

(Schematic, not to scale)





Legend: (



P-1 Approximate Location of BMP Testing



B-1 Approximate Location of Deep Boring



Delineation by Project Engineer

Plate 1



(909) 370-0474 Fax (909) 370-3156

LOG OF BORING P-1

Project: Weka, Inc.

Logged By: John F. Boring Diam.: 8" HSA Date: May 10,2024

_							
Standard Penetration (Blows per Ft.) Sample Type	Water Content in %	Dry Density in PCF	Percent Compaction	Unified Classification System	Graphic	Depth in Feet	Description and Remarks
				SM SP-SM		10	SAND - tan, silty, fine to medium, scattered pebbles - color change to yellowish tan, slightly silty, fine to medium, traces of clay, slightly lumpy, pebbles, scattered rock fragments, dry - End of infiltration test boring @ 5.0 ft. - no bedrock - no groundwater - 3" perforated socked PVC pipe installed with gravel at bottom
						25	

Groundwater: n/a	Site Location	Plate #
Approx. Depth of Bedrock: n/a		
Datum: n/a	Proposed Truck Tractor Facility	
Elevation: n/a	Waalew Road	
	Apple Valley, California	



(909) 370-0474 Fax (909) 370-3156

LOG OF BORING P-2

Project: Weka, Inc.Job No.:24019-BMPLogged By: John F.Boring Diam.:8" HSADate:May 10,2024

Description and Remarks Content Content					
SP-SM Surface weeds SAND - light brown to gray brown, slightly silty, fine to medium, scattered pebbles, damp SC - clavey, lumpy, damp to moist	Standard Penetration (Blows per Ft.) Sample Type	in % Dry Density in PCF	Percent Compaction Unified Classification System	Graphic Depth in	Description and Remarks
- End of infiltration test boring @ 5.0 ft no bedrock - no groundwater - 3" perforated socked FVC pipe installed with gravel at bottom 10 15 25 30					SAND - light brown to gray brown, slightly silty, fine to medium, scattered pebbles, damp - clayey, lumpy, damp to moist - End of infiltration test boring @ 5.0 ft no bedrock - no groundwater - 3" perforated socked PVC pipe installed with gravel at bottom

Groundwater: n/a	Site Location	Plate #
Approx. Depth of Bedrock: n/a		
Datum: n/a	Proposed Truck Tractor Facility	
	Waalew Road	
Elevation: n/a	Apple Valley, California	



(909) 370-0474 Fax (909) 370-3156

LOG OF BORING P-3

Project: Weka, Inc.

Logged By: John F. Boring Diam.: 8" HSA Date: May 10,2024

Loggod Dy.			71119	
Standard Penetration (Blows per Ft.) Sample Type Water Content in %	Dry Density in PCF Percent Compaction	Unified Classification System	Graphic Depth in Feet	Description and Remarks
		SP-SM 1 1 1 1 1 1 1 1 1	10 15 20 25	SAND - yellow tan brown, slightly silty, fine to medium, slightly lumpy, occasional pebbles, dry to damp - End of infiltration test boring @ 5.0 ft. no bedrock no groundwater 3" perforated socked PVC pipe installed with gravel at bottom

Groundwater: n/a	Site Location	Plate #
Approx. Depth of Bedrock: n/a		
Datum: n/a	Proposed Truck Tractor Facility	
	Waalew Road	
Elevation: n/a	Apple Valley, California	



(909) 370-0474 Fax (909) 370-3156

LOG OF BORING B-1

Project: Weka, Inc.Job No.: 24019-BMPLogged By:John F.Boring Diam.:8" HSADate:May 10,2024

	The second second second second					
Standard Penetration (Blows per Ft.) Sample Type Water Content in %	Dry Density in PCF	Percent Compaction	Unified Classification System	Graphic	Depth in Feet	Description and Remarks
			SM-SC		10 15 20 25 30	<pre>surface weeds SAND - tan brown, slightly silty, fine to medium, pebbles, dry - color change to grayish tan brown, fine to medium, occasional pebbles - color change to tan, slightly clayey and silty, lumpy, fine to medium, damp - with pebbles, occasional rock fragments, dry - color change to yellow, silty, lumpy, fine to medium, pebbles, rock fragments, scattered rock 1/2"-1", dry - End of deep exploratory boring @ 15.0 ft. no bedrock no groundwater</pre>

Groundwater: n/a	Site Location	Plate #
Approx. Depth of Bedrock: n/a		
Datum: n/a	Proposed Truck Tractor Facility	
No. No. of the Control of the Contro	Waalew Road	
Elevation: n/a	Apple Valley, California	

KEY TO SYMBOLS

Symbol Description

Strata symbols

Silty sand

Poorly graded sand

with silt

Clayey sand

Poorly graded clayey silty sand

Notes:

- 1. Exploratory borings were drilled on May 10,2024 using a 4-inch diameter continuous flight power auger.
- 2. No free water was encountered at the time of drilling or when re-checked the following day.
- 3. Boring locations were taped from existing features and elevations extrapolated from the final design schematic plan.
- 4. These logs are subject to the limitations, conclusions, and recommendations in this report.
- 5. Results of tests conducted on samples recovered are reported on the logs.

Conversion Table (Porchet Method) Weka, Inc.

Waalew Road w/o Navajo Road, Apple Valley Project No. 24019-BMP

Test N	Test Hole Depth	Time	Initial Depth	Final Depth	Initial Water Height	Final Water Height	Change Height/Time	Average Head Height/Time
no.	(inches)	Interval	(inches)	(inches)	(inches)	(inches)		
	D _T	Δ_{T}	Do (in)	D _f (in)	H _o =D _T -D _o	$H_f = D_T - D_f$	Δ H/ Δ D= H _O -H _f	$Havg = (H_0 + H_f)/2$
P-1	60	10	36	38.5	24	21.5	2.5	22.75
P-2	60	30	36	36	24	24	0	24
P-2	60	30	36	40	24	20	4	22

	Observed Infiltration Rate (It) = Δ H60r/ Δ t (r+2Havg)					
	А	В	С			
	ΔH60r	$\Delta t (r+2H_{avg})$	A/B= inch/hr			
P-1	600	495	1.21			
P-2	0	1560	0.00			
P-3	960	1440	0.67			

Legend

 $\Delta H/\Delta D$ = Observed Field Rate

H_O = inches of water filled from bottom

 D_0 = initial height of water (inches) from bottom

 D_f = final heigh of water (inches) from bottom

Columns A-B-C: Porchet Conversion Calculations

Column C: Observed Rate following Porchet Conversion

 D_t = depth of test hole bottom (inches)

			Per	colation Tes	st Data Shee	t 1	JORTH
Proje	ect: WEK	+ ilne L	NAALEI	NRO. APP	LE VALLEY.	Project No. 2	4019-BMP
Test	Hole No:		P-D		Tested By: 🤘	Tested By: RM Date: S-1	
Dept	h of Test Ho	ole, D _T	60		USCS Soil Class	ification	
Test	Hole Dimen	sions (inche	es)			Length	Width
Dian	neter (if rou	nd)=	8.0 in.	Sides (if rectai	ngular)=		
Sandy Soil Criteria Test *							
			Δt	D _o	D _f	ΔD	Greater Than
			Time	Initial	Final	Change in	or Equal to
Trial			Interval	Depth to	Depth to	Water	6.0 inches???
No.	Start Time	Stop Time	(min)	Water (in.)	Water (in.)	Level (in.)	(Y/N)
1	10:30	10855	25	36	21	15	Y
2	10:57	1622	25	36	48,5	12.5	4
* If to	vo consective	e measureme	ents show	that six inches o	of water seeps aw	ay in less than	,
25 m	inutes, the te	st shall be ru	n for an a	dditional hour w	vith measuremer	its taken every 1	.0 minutes.
Othe	rwise, pre-so	ak (fiill) over	night. Obt	ain at least twel	lve measurement	ts per hole over	at least
six ho	urs (approxi	mately 30 mi	nute inter	vals) with a pred	cision of at least (0.25."	
			Δt	D _o	D _f	ΔD	ΔT/ΔD
			Time	Initial	Final	Change in	Percolation
Trial			Interval	Depth to	Depth to	Water	Rate
No.	Start Time	Stop Time	(min)	Water (in.)	Water (in.)	Level (in.)	(min./in.)
1	11.23	[C. 1]	10	36	42.0	6	1.67
2	11.35	11:45	10	36	40.0	4	2.50
3	11:45	11:55	10	36	38.5	25.	4.00
4	11:55	12:05	10	76	38.5	2.5	4,00
	4	4		7			

21X 11C	in thous (approximately 50 militude intervals) with a precision of at reast 0.25.						
			Δt	D _o	D _f	ΔD	ΔΤ/ΔD
			Time	Initial	Final	Change in	Percolation
Trial			Interval	Depth to	Depth to	Water	Rate
No.	Start Time	Stop Time	(min)	Water (in.)	Water (in.)	Level (in.)	(min./in.)
1	11.23	11:33	10	36	42.0	6	1.67
2	11.35	11:45	10	36	40.0	4	2.50
3	11:45	11:55	10	36	38.5	25.	4.00
4	11.55	12:05	10	.76	38.5	2.5	4.00
5	15:02	12:15	10	SE	38.5	2.5	4.00
6	12:15	12:25	10	36	28.5	2-5	4.00
7	12:25	12:25	10	36	38.5	2-5	4.00
8	12:37	12:47	10	36	38-5	2.5	4.00
9							
10							
11							
12							
13							
14							
15							
16					2		
17							
18							

Comments

			Per	colation Te	st Data Shee	et (CENTER	1
Project: WEKA INC LUARLEW RD. APPLEVALLEY Project No. 24079-BMP						1		
	Hole No:			Tested By: R		Date: 5-10-24	1	
	th of Test H	ole, D _T	60			USCS Soil Classification		
Test	Hole Dimer	nsions (inch				Length	Width	1
	neter (if rou		8.0 in.	Sides (if recta	ngular)=			1
Sand	ly Soil Crite	ria Test *		<u> </u>				1
			Δt	D _o	D_{f}	ΔD	Greater Than	1
			Time	Initial	Final	Change in	or Equal to	
Trial			Interval	Depth to	Depth to	Water	6.0 inches???	
No.	Start Time	Stop Time	(min)	Water (in.)	Water (in.)	Level (in.)	(Y/N)	
1	1	10:29	25	36	36	國家	N	
2	10:59	11:24	25	36	26	0	W	
1					of water seeps av			
K .					vith measuremer	-		
		A THE PERSON NO.			lve measuremen	•	at least	
six ho	urs (approxi	mately 30 m	inute inter	vals) with a pred	cision of at least	0.25."	-	_
	R		Δt	D _o	D _f	ΔD	ΔΤ/ΔD	_
			Time	Initial	Final	Change in	Percolation	
Trial	2		Interval	Depth to	Depth to	Water	Rate	
No.	Start Time	Stop Time	(min)	Water (in.)	Water (in.)	Level (in.)	(min./in.)	
1	11.24	11:54	130	36.25	36.25	0.25		_
2	11:54	12:24	30	3625	36.85	0.00		1
3	2.27	12:54	:30	36,25	36.25	0.00		NO REFILL
4	12:54	12:24	:30	3 6,25	36.25	0.00		REFILL
5	1:24	2054	30	3625	36.25	0.00		
6	1:54	2:24	:20	3 6.25	36.5	0.5		
7	2:24	2:54	130	36.5	36.5	() · (2)	· ·	
8	2:54	3:24	:30	J625	36.5	0.0		
9	3:24	3:54	:30	36.5	36.5	0.0		
10	3:54	4:24	01:	36.5	365	0-0		
11								
12								
13					3			
14					·			
15								
16								
17					2			
18								¥
Comn	nents	,•						

**************************************	Percolation Test Data Sheet						
Dvoi	at lileV	<u> </u>				· Contraction of the contraction	MUITT
	ect: WEK Hole No:	t ling i	P-3	JRO. APP	Tested By: R		9019-BMP Date: 5-10-24
	th of Test H	ole D			USCS Soil Classification		
			60	<u> </u>	USCS SOII Class	T	Twidth
	note Dimer	nsions (inch	8.0 in.	Sides (if recta		Length	Width
	ly Soil Criter		10.0 111.	Joines (II recta	ilgulal J-	Ĺ	
Sant)	16 1636	Δt	Do	D_f	ΔD	Greater Than
			Time	Initial	Final	Change in	or Equal to
Trial			Interval	Depth to	Depth to	Water	6.0 inches???
No.	Start Time	Stop Time	(min)	Water (in.)	Water (in.)	Level (in.)	(Y/N)
1	10:40	11:05	25	36	45	ġ	У
2	11:05	11:30	25	36	41	55	N
* If t	vo consectiv	e measureme	ents show		of water seeps aw	ay in less than	
25 m	inutes, the te	est shall be ru	ın for an a	dditional hour w	vith measuremer	its taken every :	10 minutes.
Othe	rwise, pre-so	ak (fiill) over	night. Ob	tain at least twe	lve measuremen	ts per hole over	at least
six ho	urs (approxi	mately 30 mi	nute inter	vals) with a pred	cision of at least (0.25."	
			Δt	D _o	D _f	ΔD	ΔΤ/ΔD
			Time	. Initial	Final	Change in	Percolation
Trial			Interval	Depth to	Depth to	Water	Rate
No.	Start Time	Stop Time	(min)	Water (in.)	Water (in.)	Level (in.)	(min./in.)
1	11-30	12:00	30	36	42	6	1.67-50
2	12:00	12:30	02:	36	41	6	5.00
3	12:32	1:02	:30	36	41	5	6.60
4	1:08	138	150	56	41	5	6.00
5	1:38	208	:30	36	.41	**Omenda	6.00
6	2:08	2:38	:70	36	40,5	4.5	6.67
7	2:38	3:08	:30	36	40.5	4.5	6.67
8	3:08	3:38	130	36	40.0	4.0	7.50
9	3.70	4:08	: 30	36	40.0	4.0	7.50
10	408	4.38	:30	36	40:0	4,0	7.50
11							
12		Non-veg markelling					
13							
14							
15							
16							
17					1		
18							
Comn	nents			<u></u>		and the second s	

1.

Form 4.3-3 Infiltration LID BMP - including underground BMPs (DA 1)			
Remaining LID DCV not met by site design BMP (ft³): V _{unme}	_{set} = Form 4.2-1 Item 7 -	- Form 4.3-2 Item19	·
BMP Type Use columns to the right to compute runoff volume retention from proposed infiltration BMP (select BMP from Table 5-4 in TGD for WQMP) - Use additional forms for more BMPs	DA DMA BMP Type	DA DMA BMP Type	DA DMA BMP Type (Use additional forms for more BMPs)
Infiltration rate of underlying soils (in/hr) See Section 5.4.2 and Appendix C of the TGD for WQMP for minimum requirements for assessment methods	1.21	0,0	0.67
3 Infiltration safety factor See TGD Section 5.4.2 and Appendix D			
Design percolation rate (in/hr) Pdesign = Item 2 / Item 3			
5 Ponded water drawdown time (hr) Copy Item 6 in Form 4.2-1			
6 Maximum ponding depth (ft) BMP specific, see Table 5-4 of the TGD for WQMP for BMP design details			
7 Ponding Depth (ft) $d_{BMP} = Minimum of (1/12*Item 4*Item 5) or Item 6$			
8 Infiltrating surface area, SA_{BMP} (ft²) the lesser of the area needed for infiltration of full DCV or minimum space requirements from Table 5.7 of the TGD for WQMP			
Amended soil depth, d_{media} (ft) Only included in certain BMP types, see Table 5-4 in the TGD for WQMP for reference to BMP design details			
10 Amended soil porosity			
$^{f 11}$ Gravel depth, d_{media} (ft) Only included in certain BMP types, see Table 5-4 of the TGD for WQMP for BMP design details			
12 Gravel porosity			
13 Duration of storm as basin is filling (hrs) Typical ~ 3hrs			
Above Ground Retention Volume (ft ³) $V_{retention} = Item 8 * [Item7 + (Item 9 * Item 10) + (Item 11 * Item 12) + (Item 13 * (Item 4 / 12))]$			
15 Underground Retention Volume (ft³) Volume determined using manufacturer's specifications and calculations			
16 Total Retention Volume from LID Infiltration BMPs: (Sum	of Items 14 and 15 for	r all infiltration BMP inc	cluded in plan)
17 Fraction of DCV achieved with infiltration BMP: % Retention	ion% = Item 16 / Form	4.2-1 Item 7	140000000000000000000000000000000000000
18 Is full LID DCV retained onsite with combination of hydrologic soull fyes, demonstrate conformance using Form 4.3-10; If no, then reduce Item 3, Fact the portion of the site area used for retention and infiltration BMPs equals or excellent the applicable category of development and repeat all above calculations.	actor of Safety to 2.0 and	d increase Item 8, Infiltrat	ating Surface Area, such that

GRAIN SIZE DISTRIBUTION

Project: Weka, Inc. Job # 24019-BMP


Location: Waalew Rd. w/o Navajo Rd, Apple Valley Boring No: P-2 @ 5.0 ft Sample No: 2

Description of Soil: SP

Date of Sample: 5/10/2024

Tested By: JF Date of Testing: 5/14/2024

Sieve No.	Sieve Openings in mm	Percent Finer	Grain Size	% Retained
4	4.76	99.66	Gravel	0.5
10	2.38	85.18	Med. to Crs	60.5
20	0.84	57.66	Fines	33
40	0.42	36.36	Silts/Clays	6
60	0.28	23.46		
100	0.149	13.56		
200	0.074	5.76		



Visual Soil Description:

SAND - fine to coarse with traces of silts, pebbles.

Soil Classification: SP

System: USC

SOILS SOUTHWEST INC.Consulting Foundation Engineers

Expansion Index

ASTM D 4829

Machine No:

1

Weka Inc.

Project No:

24019-F

Project Name: Lot/Boring/Trench: P2

Tract No:

Depth (ft):

5 ft.

Location: Waalew Road, Apple Valley

Technician:

JF

Date: 5-13-24

TEST DATA		Load: 144 lb	Ring = 1" x 4"
	Dial Reading	Time (h:m)	Date
Dry / 10 min	0	2:55	5/13/2024
Inundate	0	3:05	5/13/2024
Reading	16	3:15	5/13/2024
Reading	41.0	4:15	5/13/2024
Reading	45.0	4:35	5/13/2024
El (measured)	52.0	8:22	5/14/2024

DEGREE OF SATURATION DATA	Test A	Test B
A. Initial Moisture Content (%)	17.14%	13.44%
B. Weight of wet soil + Ring (g)	609.20	590.40
C. Weight of Ring (g)	188.70	188.70
D. Weight of Wet Soil (g) (B-C)	420.50	401.70
E. Weight of Dry Soil (g) (D/(1 + A))	358.97	354.11
F. Wet Density (pcf) D g/cubic cm/207 cubic cm convert to		
pcf (x 62.4) (1gram/cubic cm = 62.4 lbs cubic foot)	126.76	121.09
G. Dry Density (pcf) E g/cubic cm/207 cubic cm convert to pcf		
(x 62.4)	108.21	106.75
H. Weight of Water (pcf) (A/100 x G)	18.55	14.35
I. Volume of Solids (cubic ft) (G/(2.7 sp. Gravity x 62.4))	0.64	0.63
J. Volume of Voids (cubic ft) (1-I)	0.36	0.37
Degree of saturation (%) Volume of water/volume of void x 100		
H/62.4/J (%)	83.09	62.75

Expansion Potential					
	Test A	Test B			
0 - 20	N/A	\leftrightarrow	VERY LOW		
21 - 50	N/A	\leftrightarrow	LOW		
51 - 90	N/A	\leftrightarrow	MEDIUM		
91 - 130	N/A	N/A	HIGH		
>130	N/A	N/A	VERY HIGH		

FINAL RESULTS					
Expansion Index (El60) (A)		Final Moisture Content (%) 26.5			
Expansion Index (El60) (B)	61.00	← Note: Disregard Test (B) if Degree of Saturation is 0.0			

CORRECTION FOR DEGREE OF SATURATION

El60 = El measured - (50-S measured) x ((65 + El measured) / (220 - S measured))