

**GEOTECHNICAL INVESTIGATION  
PROPOSED INDUSTRIAL DEVELOPMENT**

NWC Central Road and Corwin Road

Apple Valley, California

for

Lake Creek Industrial, LLC



**SOUTHERN  
CALIFORNIA  
GEOTECHNICAL**  
*A California Corporation*

July 11, 2022

Lake Creek Industrial, LLC  
1302 Brittany Cross Road  
Santa Ana, California 92705



**SOUTHERN  
CALIFORNIA  
GEOTECHNICAL**  
*A California Corporation*

Attention: Mr. Mike Tonkonogy  
Manager

Project No.: **22G153-1**

Subject: **Geotechnical Investigation**  
Proposed Apple Valley Assemblage  
NWC Central Road and Corwin Road  
Apple Valley, California

Mr. Tonkonogy:

In accordance with your request, we have conducted a geotechnical investigation at the subject site. We are pleased to present this report summarizing the conclusions and recommendations developed from our investigation.

We sincerely appreciate the opportunity to be of service on this project. We look forward to providing additional consulting services during the course of the project. If we may be of further assistance in any manner, please contact our office.

Respectfully Submitted,

**SOUTHERN CALIFORNIA GEOTECHNICAL, INC.**

Daniel W. Nielsen, GE 3166  
Senior Engineer



Robert G. Trazo, M.Sc., GE 2655  
Principal Engineer



Distribution: (1) Addressee

# TABLE OF CONTENTS

<b>1.0 EXECUTIVE SUMMARY</b>	<b>1</b>
<b>2.0 SCOPE OF SERVICES</b>	<b>3</b>
<b>3.0 SITE AND PROJECT DESCRIPTION</b>	<b>4</b>
3.1 Site Conditions	4
3.2 Proposed Development	4
<b>4.0 SUBSURFACE EXPLORATION</b>	<b>6</b>
4.1 Scope of Exploration/Sampling Methods	6
4.2 Geotechnical Conditions	6
<b>5.0 LABORATORY TESTING</b>	<b>8</b>
<b>6.0 CONCLUSIONS AND RECOMMENDATIONS</b>	<b>11</b>
6.1 Seismic Design Considerations	11
6.2 Geotechnical Design Considerations	13
6.3 Site Grading Recommendations	15
6.4 Construction Considerations	18
6.5 Foundation Design and Construction	18
6.6 Floor Slab Design and Construction	20
6.7 Retaining Wall Design and Construction	21
6.8 Pavement Design Parameters	23
<b>7.0 GENERAL COMMENTS</b>	<b>26</b>
<b>APPENDICES</b>	
A Plate 1: Site Location Map Plate 2: Boring Location Plan	
B Boring Logs	
C Laboratory Test Results	
D Grading Guide Specifications	
E Seismic Design Parameters	

## 1.0 EXECUTIVE SUMMARY

---

Presented below is a brief summary of the conclusions and recommendations of this investigation. Since this summary is not all inclusive, it should be read in complete context with the entire report.

### Site Preparation Recommendations

- Site stripping will be necessary to remove the native grass, shrub and tree growth which is present throughout the majority of the site. All vegetation and any organic topsoil should be removed during site stripping.
- The near surface soils encountered at the boring locations consist of native alluvium. The near surface soils possess variable densities and strengths, and the results of laboratory testing indicate that some of the soils within the upper 5 to 6± feet possess significant collapse potential. Additionally, the proposed grading at the site will likely result in cut/fill transitions within the proposed building pad areas. Based on these considerations, remedial grading is recommended to be performed within the proposed building areas to provide more consistent support characteristics throughout the proposed building areas.
- Based on their variable relative densities and the potential for consolidation settlement and hydrocollapse, remedial grading is recommended to be performed within the proposed building pad areas. The existing soils within the proposed building areas should be overexcavated to a depth of 5 feet below existing grades and to a depth of 5 feet below proposed pad grades. The proposed foundation influence zones should be overexcavated to a depth of at least 3 feet below proposed foundation bearing grade. The overexcavation should also extend to a sufficient depth to remove any artificial fill soils.
- After overexcavation has been completed, the resulting subgrade soils should be evaluated by the geotechnical engineer to identify any additional soils that should be overexcavated. The resulting soils should be scarified and moisture conditioned (and thoroughly flooded) to achieve a moisture content of 0 to 4 percent above optimum moisture, to a depth of at least 12 inches. The overexcavation subgrade soils should then be recompacted under the observation of the geotechnical engineer. The previously excavated soils may then be replaced as compacted structural fill. New fill soils placed at depths greater than 12± feet below proposed grades should be compacted to at least 95 percent of the ASTM D-1557 maximum dry density.
- The new pavement and flatwork subgrade soils are recommended to be scarified to a depth of 12± inches, thoroughly moisture conditioned and recompacted to at least 90 percent of the ASTM D-1557 maximum dry density.

### Building Foundation Recommendations

- Spread footing foundations, supported in newly placed structural fill soils.
- Maximum, net allowable soil bearing pressure: 2,500 lbs/ft<sup>2</sup>.
- Reinforcement consisting of at least two (2) No. 5 rebars (1 top and 1 bottom) in strip footings. Additional reinforcement may be necessary for structural considerations.

### Building Floor Slab Recommendations

- Conventional Slab on Grade, at least 6 inches thick

- Modulus of Subgrade Reaction:  $k = 150$  psi/in
- Reinforcement is not considered to be necessary for geotechnical considerations.
- The actual thickness and reinforcement of the floor slabs should be determined by the structural engineer, based on the imposed slab loading.

### Pavements

<b>ASPHALT PAVEMENTS (R=40)</b>					
<b>Materials</b>	<b>Thickness (inches)</b>				
	Auto Parking and Auto Drive Lanes (TI = 4.0 to 5.0)	Truck Traffic			
		TI = 6.0	TI = 7.0	TI = 8.0	TI = 9.0
Asphalt Concrete	3	3½	4	5	5½
Aggregate Base	4	6	7	8	10
Compacted Subgrade	12	12	12	12	12

<b>PORTLAND CEMENT CONCRETE PAVEMENTS (R=40)</b>				
<b>Materials</b>	<b>Thickness (inches)</b>			
	Autos and Light Truck Traffic (TI = 6.0)	Truck Traffic		
		TI = 7.0	TI = 8.0	TI = 9.0
PCC	5	5½	6½	8
Compacted Subgrade (95% minimum compaction)	12	12	12	12

## **2.0 SCOPE OF SERVICES**

---

The scope of services performed for this project was in accordance with our Proposal No. 22P160, dated March 8, 2022. The scope of services included a visual site reconnaissance, subsurface exploration, field and laboratory testing, and geotechnical engineering analysis to provide criteria for preparing the design of the building foundations, building floor slabs, and parking lot pavements along with site preparation recommendations and construction considerations for the proposed development. The evaluation of the environmental aspects of this site was beyond the scope of services for this geotechnical investigation.

## **3.0 SITE AND PROJECT DESCRIPTION**

---

### **3.1 Site Conditions**

The subject site is located at the northwest corner of Central Road and Corwin Road in Apple Valley, California. The site is bounded to the north by Gustine Road, to the west by the Apple Valley Airport, to the south by Corwin Road, and to the east by Central Road. The general location of the site is illustrated on the Site Location Map, included as Plate 1 of this report.

The site comprises of several contiguous parcels, which total 288± acres in size. The site is vacant and undeveloped. Two (2) north-south trending dirt roads are present in the western and central areas of the site. A fire hydrant is present near the western dirt road. Ground surface cover throughout the site consists of exposed soils with sparse vegetation growth throughout.

Detailed topographic information was not available at the time of this report. Based on elevations obtained from Google Earth and visual observations made at the time of the subsurface investigation, the overall site slopes downward toward the southwest at a gradient of about 2± percent. The site topography is slightly rolling, with several northeast to southwest trending drainage courses. The depths of these drainage courses with respect to the adjacent grade were estimated to be as much as 2 to 3± feet. There is about 105± feet of elevation differential across the site.

### **3.2 Proposed Development**

Based on a site plan (A1-02) provided by the client, the site is expected to be developed with four (4) warehouses. The approximate building sizes are described below:

<b><u>Building No.</u></b>	<b><u>Size (ft<sup>2</sup>)</u></b>	<b><u>Location</u></b>
1	322,612	Northwest
2	774,013	Southwest
3	1,467,948	Central
4	1,171,496	East

The buildings are expected to include dock-high doors in the loading dock areas. We expect that the buildings will be surrounded by asphaltic concrete pavements in the parking and drive areas, Portland cement concrete pavements in the truck court areas, with isolated areas of concrete flatwork and landscape planters.

Detailed structural information was not available. It is assumed that the new buildings will be single-story structures of tilt-up concrete construction, typically supported on conventional shallow foundations with a concrete slab-on-grade floor. Based on the assumed construction, maximum column and wall loads are expected to be on the order of 100 kips and 4 to 7 kips per

linear foot, respectively.

No significant amounts of below-grade construction, such as crawl spaces or basements, are expected to be included in the proposed development. Based on the assumed topography, cuts and fills of up to 50± feet are expected to be necessary to achieve the proposed site grades.

## **4.0 SUBSURFACE EXPLORATION**

---

### **4.1 Scope of Exploration/Sampling Methods**

The subsurface exploration for this project consisted of forty-seven (47) borings advanced to depths of 10 to 30± feet below the existing site grades. All of the borings were logged during drilling by a member of our staff.

The borings were advanced with hollow-stem augers, by a conventional truck-mounted drilling rig. Representative bulk and relatively undisturbed soil samples were taken during drilling. Relatively undisturbed samples were taken with a split barrel "California Sampler" containing a series of one-inch-long, 2.416± inch diameter brass rings. This sampling method is described in ASTM Test Method D-3550. Samples were also taken using a 1.4±-inch inside diameter split spoon sampler, in general accordance with ASTM D-1586. Both of these samplers are driven into the ground with successive blows of a 140-pound weight falling 30 inches. The blow counts obtained during driving are recorded for further analysis. Bulk samples were collected in plastic bags to retain their original moisture content. The relatively undisturbed ring samples were placed in molded plastic sleeves that were then sealed and transported to our laboratory.

The approximate locations of the borings are indicated on the Boring Location Plan, included as Plate 2 in Appendix A of this report. The Boring Logs, which illustrate the conditions encountered at the boring locations, as well as the results of some of the laboratory testing, are included in Appendix.

### **4.2 Geotechnical Conditions**

#### Alluvium

Native alluvium was encountered at the ground surface at all the borings locations, extending to at least the maximum depth explored of 30± feet below surface grade. The soils encountered within the upper 2½ to 6½± feet at some of the boring logs were classified as younger alluvium, (denoted as "alluvium" on the boring logs). These younger alluvial soils generally consist of loose to dense sands, silty sands, and sandy silts. Older native alluvial soils were encountered at all of the boring locations, either at the ground surface or beneath the younger alluvial soils, where present. The older alluvial soils generally consist of medium dense to very dense silty sands, sands, sandy silts, clayey sands, and occasional layers of stiff to hard sandy clays. In general, the older alluvial soils were observed to be weakly cemented.

#### Groundwater

Free water was not encountered during the drilling of any of the borings. Based on the lack of any water within the borings, and the moisture contents of the recovered soil samples, the static

groundwater table is considered to have existed at a depth in excess of 30± feet at the time of the subsurface exploration.

Historic and recent water level data was obtained from the California Department of Water Resources website, <http://www.water.ca.gov/waterdatalibrary/>. One monitoring well on record is located 3000± feet southeast of the site. Water level readings within this monitoring well indicates a high groundwater level of 240± feet below ground surface in March 2017.

## **5.0 LABORATORY TESTING**

---

The soil samples recovered from the subsurface exploration were returned to our laboratory for further testing to determine selected physical and engineering properties of the soils. The tests are briefly discussed below. It should be noted that the test results are specific to the actual samples tested, and variations could be expected at other locations and depths.

### Classification

All recovered soil samples were classified using the Unified Soil Classification System (USCS), in accordance with ASTM D-2488. Field identifications were then supplemented with additional visual classifications and/or by laboratory testing. The USCS classifications are shown on the Boring Logs and are periodically referenced throughout this report.

### Density and Moisture Content

The density has been determined for selected relatively undisturbed ring samples. These densities were determined in general accordance with the method presented in ASTM D-2937. The results are recorded as dry unit weight in pounds per cubic foot. The moisture contents are determined in accordance with ASTM D-2216, and are expressed as a percentage of the dry weight. These test results are presented on the Boring Logs.

### Consolidation

Selected soil samples have been tested to determine their consolidation potential, in accordance with ASTM D-2435. The testing apparatus is designed to accept either natural or remolded samples in a one-inch high ring, approximately 2.416 inches in diameter. Each sample is then loaded incrementally in a geometric progression and the resulting deflection is recorded at selected time intervals. Porous stones are in contact with the top and bottom of the sample to permit the addition or release of pore water. The samples are typically inundated with water at an intermediate load to determine their potential for collapse or heave. The results of the consolidation testing are plotted on Plates C-1 through C-17 in Appendix C of this report.

### Maximum Dry Density and Optimum Moisture Content

Three representative bulk samples have been tested for their maximum dry densities and optimum moisture contents. The results have been obtained using the Modified Proctor procedure, per ASTM D-1557 and are presented on Plates C-18, C-19, and C-20 in Appendix C of this report. This test is generally used to compare the in-situ densities of undisturbed field samples, and for later compaction testing. Additional testing of other soil types or soil mixes may be necessary at a later date.

### Soluble Sulfates

Representative samples of the near-surface soils were submitted to a subcontracted analytical laboratory for determination of soluble sulfate content. Soluble sulfates are naturally present in

soils, and if the concentration is high enough, can result in degradation of concrete which comes into contact with these soils. The results of the soluble sulfate testing are presented below, and are discussed further in a subsequent section of this report.

<u>Sample Identification</u>	<u>Soluble Sulfates (%)</u>	<u>Sulfate Classification</u>
B-18 @ 0 to 5 feet	0.004	Not Applicable (S0)
B-27 @ 0 to 5 feet	0.006	Not Applicable (S0)
B-32 @ 0 to 5 feet	0.002	Not Applicable (S0)
B-34 @ 0 to 5 feet	0.005	Not Applicable (S0)

### Corrosivity Testing

Representative bulk samples of the near-surface soils were submitted to a subcontracted corrosion engineering laboratory to determine if the near-surface soils possess corrosive characteristics with respect to common construction materials. The corrosivity testing included a determination of the electrical resistivity, pH, and chloride and nitrate concentrations of the soils, as well as other tests. The results of some of these tests are presented below.

<u>Sample Identification</u>	<u>Saturated Resistivity (ohm-cm)</u>	<u>pH</u>	<u>Chlorides (mg/kg)</u>	<u>Nitrates (mg/kg)</u>
B-18 @ 0 to 5 feet	4,891	8.9	20.7	15.0
B-27 @ 0 to 5 feet	6,432	9.1	33.1	4.6
B-32 @ 0 to 5 feet	5,025	8.6	12.0	8.3
B-34 @ 0 to 5 feet	10,050	9.0	18.8	4.8

### R-value

R-value testing was performed on three (5) representative bulk sample of the near-surface soils. The R-value was determined in accordance with CA Test Method 301. This test provides a measure of the pavement support characteristics of the soils and is used in the pavement thickness design procedure. The results of the R-value testing are presented below:

<u>Sample ID</u>	<u>R-Value</u>
B-20 @ 0 to 5 feet	68
B-32 @ 0 to 5 feet	65

### Direct Shear

Direct shear testing was performed on two (2) selected soil samples to determine their shear strength parameters. The testing was performed in accordance with ASTM D-3080. The testing apparatus is designed to accept either natural or remolded samples in a one-inch high ring, approximately 2.416 inches in diameter. Testing is performed on three samples which are loaded with different normal loads and the resulting shear strength is determined for that particular

normal load. The shearing of the samples is performed at a rate slow enough to permit the dissipation of excess pore water pressure. Porous stones are in contact with the top and bottom of the sample to permit the addition or release of pore water. The results of the direct shear tests are presented on Plates C-21 and C-22.

## **6.0 CONCLUSIONS AND RECOMMENDATIONS**

---

Based on the results of our review, field exploration, laboratory testing and geotechnical analysis, the proposed development is considered feasible from a geotechnical standpoint. The recommendations contained in this report should be taken into the design, construction, and grading considerations.

The recommendations are contingent upon all grading and foundation construction activities being monitored by the geotechnical engineer of record. The recommendations are provided with the assumption that an adequate program of client consultation, construction monitoring, and testing will be performed during the final design and construction phases to verify compliance with these recommendations. Maintaining Southern California Geotechnical, Inc., (SCG) as the geotechnical consultant from the beginning to the end of the project will provide continuity of services. The geotechnical engineering firm providing testing and observation services shall assume the responsibility of Geotechnical Engineer of Record.

The Grading Guide Specifications, included as Appendix D, should be considered part of this report, and should be incorporated into the project specifications. The contractor and/or owner of the development should bring to the attention of the geotechnical engineer any conditions that differ from those stated in this report, or which may be detrimental for the development.

### **6.1 Seismic Design Considerations**

The subject site is located in an area which is subject to strong ground motions due to earthquakes. The performance of a site-specific seismic hazards analysis was beyond the scope of this investigation. However, numerous faults capable of producing significant ground motions are located near the subject site. Due to economic considerations, it is not generally considered reasonable to design a structure that is not susceptible to earthquake damage. Therefore, significant damage to structures may be unavoidable during large earthquakes. The proposed structures should, however, be designed to resist structural collapse and thereby provide reasonable protection from serious injury, catastrophic property damage and loss of life.

#### Faulting and Seismicity

Research of available maps indicates that the subject site is not located within an Alquist-Priolo Earthquake Fault Zone. Furthermore, SCG did not identify any evidence of faulting during the geotechnical investigation. Therefore, the possibility of significant fault rupture on the site is considered to be low.

The potential for other geologic hazards such as seismically induced settlement, lateral spreading, tsunamis, inundation, seiches, flooding, and subsidence affecting the site is considered low.

## Seismic Design Parameters

The California Building Code (CBC) provides procedures for earthquake resistant structural design that include considerations for on-site soil conditions, occupancy, and the configuration of the structure including the structural system and height. The seismic design parameters presented below are based on the soil profile and the proximity of known faults with respect to the subject site.

Based on standards in place at the time of this report, the proposed development is expected to be designed in accordance with the requirements of the 2019 edition of the California Building Code (CBC), which was adopted on January 1, 2020.

The 2019 CBC Seismic Design Parameters have been generated using the SEAOC/OSHPD Seismic Design Maps Tool, a web-based software application available at the website [www.seismicmaps.org](http://www.seismicmaps.org). This software application calculates seismic design parameters in accordance with several building code reference documents, including ASCE 7-16, upon which the 2019 CBC is based. The application utilizes a database of risk-targeted maximum considered earthquake ( $MCE_R$ ) site accelerations at 0.01-degree intervals for each of the code documents. The table below was created using data obtained from the application. The output generated from this program is included as Plates E-1 in Appendix E of this report. Based on this output, the following parameters may be utilized for the subject site:

### **2019 CBC SEISMIC DESIGN PARAMETERS**

Parameter		Value
Mapped $MCE_R$ Acceleration at 0.2 sec Period	$S_5$	1.047
Mapped $MCE_R$ Acceleration at 1.0 sec Period	$S_1$	0.400
Site Class	---	C
Site Modified Spectral Acceleration at 0.2 sec Period	$S_{MS}$	1.257
Site Modified Spectral Acceleration at 1.0 sec Period	$S_{M1}$	0.600
Design Spectral Acceleration at 0.2 sec Period	$S_{DS}$	0.838
Design Spectral Acceleration at 1.0 sec Period	$S_{D1}$	0.400

## Liquefaction

Liquefaction is the loss of the strength in generally cohesionless, saturated soils when the pore-water pressure induced in the soil by a seismic event becomes equal to or exceeds the overburden pressure. The primary factors which influence the potential for liquefaction include groundwater table elevation, soil type and grain size characteristics, relative density of the soil, initial confining pressure, and intensity and duration of ground shaking. The depth within which the occurrence of liquefaction may impact surface improvements is generally identified as the upper 50 feet below the existing ground surface. Liquefaction potential is greater in saturated, loose, poorly graded fine sands with a mean ( $d_{50}$ ) grain size in the range of 0.075 to 0.2 mm (Seed and Idriss, 1971). Clayey (cohesive) soils or soils which possess clay particles ( $d < 0.005\text{mm}$ ) in excess of 20

percent (Seed and Idriss, 1982) are generally not considered to be susceptible to liquefaction, nor are those soils which are above the historic static groundwater table.

The California Geological Survey (CGS) has not yet conducted detailed seismic hazards mapping in the area of the subject site. The general liquefaction susceptibility of the site was determined by research of the San Bernardino County Official Land Use Plan, General Plan, Geologic Hazard Overlay. Map EH31B for the Apple Valley North Quadrangle indicates that the subject site is not located within an area of liquefaction susceptibility. Based on the mapping performed by the county of San Bernardino and the subsurface conditions encountered at the boring locations including the lack of a static ground water table within the upper 40± feet, liquefaction is not considered to be a design concern for this project.

## **6.2 Geotechnical Design Considerations**

### General

The near surface soils encountered at the boring locations consist of loose to very dense native alluvium. These soils possess variable densities and strengths. The results of consolidation and collapse testing indicate that some of the soils in the upper 5 to 6± feet possess significant potential for collapse settlement when inundated with water. Some of the near-surface soils also possess minor to moderate potential for consolidation settlement when loaded. Based on the size of the proposed buildings, some cut/fill transitions are expected to be created during grading. Based on these considerations, remedial grading is warranted within the proposed building areas in order to remove a portion of the near-surface native alluvium and to replace these materials as compacted structural fill.

### Settlement

Laboratory testing indicates that some samples of soils taken from the upper zone of native alluvial soils possess a potential for collapse when exposed to moisture infiltration. These soils also possess a potential for moderate consolidation when exposed to load increases in the range of those that will be exerted by the foundations of the new structures. The potentially compressible and collapsible soils generally extend to depths of 5 to 6± feet. The proposed remedial grading will remove the near-surface potentially collapsible native soils from within the proposed building areas. Therefore, following completion of the recommended grading, post-construction settlements are expected to be within tolerable limits.

### Soluble Sulfates

The results of the soluble sulfate testing indicate that the selected samples of the on-site soils contain negligible concentrations of soluble sulfates, in accordance with American Concrete Institute (ACI) guidelines. Therefore, specialized concrete mix designs are not considered to be necessary, with regard to sulfate protection purposes. It is, however, recommended that additional soluble sulfate testing be conducted at the completion of rough grading to verify the soluble sulfate concentrations of the soils which are present at pad grade within the building areas.

## Expansion

The near-surface soils generally consist of silty sands, sandy silts and sands with varying gravel content. These materials have been visually classified as very low to non-expansive. Therefore, no design considerations related to expansive soils are considered warranted for this site.

## Corrosion Potential

The results of laboratory testing indicate that the tested samples of the on-site soils possess saturated resistivity values ranging between 4,891 to 10,050 ohm-cm, and pH values ranging between 8.6 and 9.1. These test results have been evaluated in accordance with guidelines published by the Ductile Iron Pipe Research Association (DIPRA). The DIPRA guidelines consist of a point system by which characteristics of the soils are used to quantify the corrosivity characteristics of the site. Sulfides, and redox potential are factors that are also used in the evaluation procedure. We have evaluated the corrosivity characteristics of the on-site soils using resistivity, pH, and moisture content. Based on these factors, and utilizing the DIPRA procedure, some of the on-site soils are considered to be mildly corrosive to ductile iron pipe. Therefore, some form of polyethylene encasement may be necessary for ductile iron pipes. However, SCG does not practice in the area of corrosion engineering. Therefore, the client may also wish to contact a corrosion engineer to provide a more thorough evaluation.

Relatively low concentrations (12.0 to 33.1 mg/kg) of chlorides were detected in the samples submitted for corrosivity testing. In general, soils possessing chloride concentrations in excess of 500 parts per million (ppm) are considered to be corrosive with respect to steel reinforcement within reinforced concrete. Based on the lack of any significant chlorides in the tested sample, the site is considered to have a C1 chloride exposure in accordance with the American Concrete Institute (ACI) Publication 318 Building Code Requirements for Structural Concrete and Commentary. Therefore, a specialized concrete mix design for reinforced concrete for protection against chloride exposure is not considered warranted.

Nitrates present in soil can be corrosive to copper tubing at concentrations greater than 50 mg/kg. The tested samples possess nitrate concentrations between 4.6 and 15.0 mg/kg. Based on these test results, the on-site soils are not considered to be corrosive to copper tubing.

It should be noted that SCG does not practice in the field of corrosion engineering. Therefore, the client may wish to contact a corrosion engineer to provide a more thorough evaluation of these test results.

## Shrinkage/Subsidence

Removal and recompaction of the near-surface native alluvial soils is estimated to result in an average shrinkage of 6 to 12± percent. Shrinkage estimates for the individual samples range between less than 1 and 17± percent based on the results of density testing and the assumption that the onsite soils will be compacted to about 92 percent of the ASTM D-1557 maximum dry density. It should be noted that the shrinkage estimate is based on the results of dry density testing performed on small-diameter samples of the existing soils taken at the boring locations. If a more accurate and precise shrinkage estimate is desired, SCG can perform a shrinkage study involving several excavated test-pits where in-place densities are determined using in-situ testing

methods instead of laboratory density testing on small-diameter samples. Please contact SCG for details and a cost estimate regarding a shrinkage study, if desired.

Minor ground subsidence is expected to occur in the soils below the zone of removal, due to settlement and machinery working. The subsidence is estimated to be 0.1± feet. This estimate may be used for grading in areas that are underlain by native alluvial soils.

These estimates are based on previous experience and the subsurface conditions encountered at the boring locations. The actual amount of subsidence is expected to be variable and will be dependent on the type of machinery used, repetitions of use, and dynamic effects, all of which are difficult to assess precisely.

### Grading and Foundation Plan Review

No grading or foundation plans were available at the time of this report. It is therefore recommended that we be provided with copies of the preliminary plans, when they become available, for review with regard to the conclusions, recommendations, and assumptions contained within this report.

## **6.3 Site Grading Recommendations**

The grading recommendations presented below are based on the subsurface conditions encountered at the boring locations and our understanding of the proposed development. We recommend that all grading activities be completed in accordance with the Grading Guide Specifications included as Appendix D of this report, unless superseded by site-specific recommendations presented below.

### Site Stripping

The native grass, shrubs and weeds as well as the trees present throughout proposed improvement areas on the site should be stripped and disposed of off-site. Stripping should include any organic soils and any root masses from trees. The actual extent of site stripping should be determined in the field by the geotechnical engineer, based on the organic content and stability of the materials encountered.

### Treatment of Existing Soils: Building Pads

Remedial grading should be performed within the proposed building areas in order to remove a portion of the near-surface native alluvial soils. Based on conditions encountered at the boring locations, the existing soils within the proposed building areas are recommended to be overexcavated to a depth of at least 5 feet below existing grade and to a depth of at least 5 feet below proposed building pad subgrade elevation, whichever is greater. The depth of overexcavation should also be sufficient to remove any artificial fill soils.

Where not encompassed within the general building pad overexcavation, additional overexcavation should be performed within the influence zones of the new foundations, to provide

for a new layer of compacted structural fill extending to a depth of 3 feet below proposed bearing grade.

The overexcavation areas should extend at least 5 feet beyond the building foundations and perimeters. If the proposed structures incorporate any exterior columns (such as for a canopy or overhang) the area of overexcavation should also encompass these areas.

Following completion of the overexcavation, the subgrade soils within the building areas should be evaluated by the geotechnical engineer to verify their suitability to serve as the structural fill subgrade, as well as to support the foundation loads of the new structures. This evaluation should include proofrolling and probing to identify any soft, loose or otherwise unstable soils that must be removed. Some localized areas of deeper excavation may be required if loose, porous, or low density native soils are encountered at the base of the overexcavation.

After a suitable overexcavation subgrade has been achieved, the exposed soils should be scarified to a depth of at least 12 inches and moisture conditioned to achieve a moisture content of 0 to 4 percent above optimum moisture content. In general, the near-surface sandy soils possess moisture contents well below the optimum moisture content for compaction. Therefore, overexcavation subgrade soils consisting predominately of sands should be thoroughly flooded. The subgrade soils should then be recompacted to at least 90 percent of the ASTM D-1557 maximum dry density. The building pad areas may then be raised to grade with previously excavated soils or imported structural fill. Any fill soils placed at depths greater than 12± feet below the proposed site grades should be compacted to at least 95 percent of the ASTM D-1557 maximum dry density.

#### Treatment of Existing Soils: Retaining Walls and Site Walls

The existing soils within the areas of any proposed retaining walls and non-retaining site walls should be overexcavated to a depth of 3 feet below foundation bearing grade and replaced as compacted structural fill, as discussed above for the proposed building pads. Any undocumented fill soils within any of these foundation areas should be removed in their entirety. The overexcavation areas should extend at least 5 feet beyond the foundation perimeters, and to an extent equal to the depth of fill below the new foundations. Any erection pads used to construct the walls are considered to be part of the foundation system with respect to these remedial grading recommendations. The overexcavation subgrade soils should be evaluated by the geotechnical engineer prior to scarifying, moisture conditioning, and recompacting the upper 12 inches of exposed subgrade soils. The previously excavated soils may then be replaced as compacted structural fill.

#### Treatment of Existing Soils: Parking and Drive Areas

Based on economic considerations, overexcavation of the existing low strength alluvium and undocumented fill soils in the new parking and drive areas is not considered warranted, with the exception of areas where lower strength or unstable soils are identified by the geotechnical engineer during grading.

Subgrade preparation in the new parking and drive areas should initially consist of removal of all soils disturbed during stripping and demolition operations. The geotechnical engineer should then

evaluate the subgrade to identify any areas of additional unsuitable soils. The subgrade soils should then be scarified to a depth of 12± inches, moisture conditioned to 0 to 4 percent above optimum, and recompacted to at least 90 percent of the ASTM D-1557 maximum dry density. Based on the presence of variable strength alluvial soils throughout the site, it is expected that some isolated areas of additional overexcavation may be required to remove zones of lower strength, unsuitable soils.

The grading recommendations presented above for the proposed parking and drive areas assume that the owner and/or developer can tolerate minor amounts of settlement within the proposed parking areas. The grading recommendations presented above do not completely mitigate the extent of existing fill soils and loose native soils in the parking areas. As such, settlement and associated pavement distress could occur. Typically, repair of such distressed areas involves significantly lower costs than completely mitigating these soils at the time of construction. If the owner cannot tolerate the risk of such settlements, the parking and drive areas should be overexcavated to a depth of 2 feet below proposed pavement subgrade elevation, with the resulting soils replaced as compacted structural fill.

#### Fill Placement

- Fill soils should be placed in thin (6± inches), near-horizontal lifts, moisture conditioned to within 0 to 4 percent above the optimum moisture content, and compacted.
- On-site soils may be used for fill provided they are cleaned of any debris to the satisfaction of the geotechnical engineer.
- All grading and fill placement activities should be completed in accordance with the requirements of the 2019 CBC and the grading code of the town of Apple Valley.
- All fill soils should be compacted to at least 90 percent of the ASTM D-1557 maximum dry density. New fill soils placed at depths greater than 12± feet below proposed grades should be compacted to at least 95 percent of the ASTM D-1557 maximum dry density.
- Compaction tests should be performed periodically by the geotechnical engineer as random verification of compaction and moisture content. These tests are intended to aid the contractor. Since the tests are taken at discrete locations and depths, they may not be indicative of the entire fill and therefore should not relieve the contractor of his responsibility to meet the job specifications.

#### Imported Structural Fill

All imported structural fill should consist of very low expansive ( $EI < 20$ ), well graded soils possessing at least 10 percent fines (that portion of the sample passing the No. 200 sieve). Additional specifications for structural fill are presented in the Grading Guide Specifications, included as Appendix D.

#### Utility Trench Backfill

In general, all utility trench backfill soils should be compacted to at least 90 percent of the ASTM D-1557 maximum dry density. It is recommended that materials in excess of 3 inches in size not be used for utility trench backfill. Compacted trench backfill should conform to the requirements of the local grading code, and more restrictive requirements may be indicated by town of Apple Valley. All utility trench backfills should be witnessed by the geotechnical engineer. The trench

backfill soils should be compaction tested where possible; probed and visually evaluated elsewhere.

Utility trenches which parallel a footing, and extending below a 1h:1v plane projected from the outside edge of the footing should be backfilled with structural fill soils, compacted to at least 90 percent of the ASTM D-1557 standard. Pea gravel backfill should not be used for these trenches.

## **6.4 Construction Considerations**

### Moisture Sensitive Subgrade Soils

The near-surface soils possess appreciable silt and occasional clay content. These soils may become unstable if exposed to significant moisture infiltration or disturbance by construction traffic. If grading occurs during a period of relatively wet weather, an increase in subgrade instability in localized areas should also be expected. The site should, therefore, be graded to prevent ponding of surface water and to prevent water from running into excavations.

### Excavation Considerations

The near surface soils are predominately granular in composition. These materials will likely be subject to caving within shallow excavations. Where caving occurs within shallow excavations, flattened excavation slopes may be sufficient to provide excavation stability. On a preliminary basis, the inclination of temporary slopes should not exceed 2h:1v. Maintaining adequate moisture content within the near-surface soils will improve excavation stability. All excavation activities on this site should be conducted in accordance with Cal-OSHA regulations.

### Groundwater

The static groundwater table at this site is considered to exist at a depth greater than 30± feet. Therefore, groundwater is not expected to impact the grading or foundation construction activities.

## **6.5 Foundation Design and Construction**

Based on the preceding grading recommendations, it is assumed that the new building pads will be underlain by structural fill soils used to replace existing fill and low-density alluvial soils. These new structural fill soils are expected to extend to depths of at least 3 feet below proposed foundation bearing grade. Based on this subsurface profile, the proposed structures may be supported on conventional shallow foundations.

### Foundation Design Parameters

New square and rectangular footings may be designed as follows:

- Maximum, net allowable soil bearing pressure: 2,500 lbs/ft<sup>2</sup>.

- Minimum wall/column footing width: 14 inches/24 inches.
- Minimum longitudinal steel reinforcement within strip footings: Two (2) No. 5 rebars (1 top and 1 bottom).
- Minimum foundation embedment: 12 inches into suitable structural fill soils, and at least 18 inches below adjacent exterior grade. Interior column footings may be placed immediately beneath the floor slab.
- It is recommended that the perimeter building foundations be continuous across all exterior doorways. Any flatwork adjacent to the exterior doors should be doweled into the perimeter foundations in a manner determined by the structural engineer.

The allowable bearing pressure presented above may be increased by one-third when considering short duration wind or seismic loads. The minimum steel reinforcement recommended above is based on geotechnical considerations; additional reinforcement may be necessary for structural considerations. The actual design of the foundations should be determined by the structural engineer.

#### Foundation Construction

The foundation subgrade soils should be evaluated at the time of overexcavation, as discussed in Section 6.3 of this report. It is further recommended that the foundation subgrade soils be evaluated by the geotechnical engineer immediately prior to steel or concrete placement. Soils suitable for direct foundation support should consist of newly placed structural fill, compacted to at least 90 percent of the ASTM D-1557 maximum dry density. Any unsuitable materials should be removed to a depth of suitable bearing compacted structural fill, with the resulting excavations backfilled with compacted fill soils. As an alternative, lean concrete slurry (500 to 1,500 psi) may be used to backfill such isolated overexcavations.

The foundation subgrade soils should also be properly moisture conditioned to 0 to 4 percent above the Modified Proctor optimum, to a depth of at least 12 inches below bearing grade. Since it is typically not feasible to increase the moisture content of the floor slab and foundation subgrade soils once rough grading has been completed, care should be taken to maintain the moisture content of the building pad subgrade soils throughout the construction process.

#### Estimated Foundation Settlements

Post-construction total and differential settlements of shallow foundations designed and constructed in accordance with the previously presented recommendations are estimated to be less than 1.0 and 0.5 inches, respectively. Differential movements are expected to occur over a 30-foot span, thereby resulting in an angular distortion of less than 0.002 inches per inch.

#### Lateral Load Resistance

Lateral load resistance will be developed by a combination of friction acting at the base of foundations and slabs and the passive earth pressure developed by footings below grade. The following friction and passive pressure may be used to resist lateral forces:

- Passive Earth Pressure: 300 lbs/ft<sup>3</sup>
- Friction Coefficient: 0.32

These are allowable values, and include a factor of safety. When combining friction and passive resistance, the passive pressure component should be reduced by one-third. These values assume that footings will be poured directly against compacted structural fill. The maximum allowable passive pressure is 2,500 lbs/ft<sup>2</sup>.

## **6.6 Floor Slab Design and Construction**

Subgrades which will support new floor slabs should be prepared in accordance with the recommendations contained in the ***Site Grading Recommendations*** section of this report. Based on the anticipated grading which will occur at this site, the floors of the new structures may be constructed as conventional slabs-on-grade supported on newly placed structural fill soils. These fill soils are expected to extend to a depth of at least 5 feet below finished pad grade. Based on geotechnical considerations, the floor slabs may be designed as follows:

- Minimum slab thickness: 6 inches.
- Modulus of Subgrade Reaction:  $k = 150$  psi/in
- Minimum slab reinforcement: Reinforcement is not required for geotechnical conditions. The actual floor slab reinforcement should be determined by the structural engineer, based upon the imposed loading.
- Slab underlayment: If moisture sensitive floor coverings will be used the minimum slab underlayment should consist of a moisture vapor barrier constructed below the entire area where such moisture sensitive floor coverings are anticipated. The moisture vapor barrier should meet or exceed the Class A rating as defined by ASTM E 1745-97 and have a permeance rating less than 0.01 perms as described in ASTM E 96-95 and ASTM E 154-88. A polyolefin material such as Stego<sup>®</sup> Wrap Vapor Barrier or equivalent will meet these specifications. The moisture vapor barrier should be properly constructed in accordance with all applicable manufacturer specifications. The need for sand and/or the amount of sand above the moisture vapor barrier should be specified by the structural engineer or concrete contractor. The selection of sand above the barrier is not a geotechnical engineering issue and hence outside our purview.
- Moisture condition the floor slab subgrade soils to 0 to 4 percent above the Modified Proctor optimum moisture content, to a depth of 12 inches. The moisture content of the floor slab subgrade soils should be verified by the geotechnical engineer within 24 hours prior to concrete placement.
- Proper concrete curing techniques should be utilized to reduce the potential for slab curling or the formation of excessive shrinkage cracks.

The actual design of the floor slabs should be completed by the structural engineer to verify adequate thickness and reinforcement.

## **6.7 Retaining Wall Design and Construction**

Small retaining walls are expected to be necessary in the area of the new truck loading docks and may also be required to facilitate the new site grades. The parameters recommended for use in the design of these walls are presented below.

### Retaining Wall Design Parameters

Based on the soil conditions encountered at the boring locations, the following parameters may be used in the design of new retaining walls for this site. We have provided parameters assuming the use of on-site soils for retaining wall backfill. The on-site soils generally consist of silty sands, sands, sandy silts, and occasional clayey sands and sandy clays. The results of direct shear testing indicate that two samples of undisturbed alluvial soils possess ultimate friction angles of 30 and 36 degrees. The following parameters are based on an internal friction angle of 30 degrees.

If desired, SCG could provide design parameters for an alternative select backfill material behind the retaining walls. The use of select backfill material could result in lower lateral earth pressures. In order to use the design parameters for the imported select fill, this material must be placed within the entire active failure wedge. This wedge is defined as extending from the heel of the retaining wall upwards at an angle of approximately 60° from horizontal. If select backfill material behind the retaining wall is desired, SCG should be contacted for supplementary recommendations.

### **RETAINING WALL DESIGN PARAMETERS**

<b>Design Parameter</b>		<b>Soil Type</b>
		On-Site Soils
Internal Friction Angle ( $\phi$ )		30°
Unit Weight		130 lbs/ft <sup>3</sup>
Equivalent Fluid Pressure:	Active Condition (level backfill)	44 lbs/ft <sup>3</sup>
	Active Condition (2h:1v backfill)	70 lbs/ft <sup>3</sup>
	At-Rest Condition (level backfill)	65 lbs/ft <sup>3</sup>

The walls should be designed using a soil-footing coefficient of friction of 0.30 and an equivalent passive pressure of 300 lbs/ft<sup>3</sup>. The structural engineer should incorporate appropriate factors of safety in the design of the retaining walls.

The active earth pressure may be used for the design of retaining walls that do not directly support structures or support soils that in turn support structures and which will be allowed to deflect. The at-rest earth pressure should be used for walls that will not be allowed to deflect.

such as those which will support foundation bearing soils, or which will support foundation loads directly.

Where the soils on the toe side of the retaining wall are not covered by a "hard" surface such as a structure or pavement, the upper 1 foot of soil should be neglected when calculating passive resistance due to the potential for the material to become disturbed or degraded during the life of the structure.

### Retaining Wall Foundation Design

The retaining wall foundations should be supported within newly placed structural fill. Foundations to support new retaining walls should be designed in accordance with the general Foundation Design Parameters presented in a previous section of this report.

### Seismic Lateral Earth Pressures

In accordance with the 2019 CBC, any retaining walls more than 6 feet in height must be designed for seismic lateral earth pressures. If walls 6 feet or more are required for this site, the geotechnical engineer should be contacted for supplementary seismic lateral earth pressure recommendations.

### Backfill Material

On-site soils may be used to backfill the retaining walls. However, all backfill material placed within 3 feet of the back-wall face should have a particle size no greater than 3 inches. The retaining wall backfill materials should be well graded.

It is recommended that a properly installed prefabricated drainage composite such as the MiraDRAIN 6000XL (or approved equivalent), which is specifically designed for use behind retaining walls, be placed against the face on the back side of the retaining walls. This material should extend from the top of the retaining wall footing to within 1 foot of the ground surface on the back side of the retaining wall. A 12-inch thick layer of a low permeability soil should be placed over the backfill to reduce surface water migration to the underlying soils.

All retaining wall backfill should be placed and compacted under engineering-controlled conditions in the necessary layer thicknesses to ensure an in-place density between 90 and 93 percent of the maximum dry density as determined by the Modified Proctor test (ASTM D1557-91). Care should be taken to avoid over-compaction of the soils behind the retaining walls, and the use of heavy compaction equipment should be avoided.

### Subsurface Drainage

As previously indicated, the retaining wall design parameters are based upon drained backfill conditions. Consequently, some form of permanent drainage system will be necessary in conjunction with the appropriate backfill material. Subsurface drainage may consist of either:

- A weep hole drainage system typically consisting of a series of 2-inch diameter holes in the wall situated slightly above the ground surface elevation on the exposed side of the

wall and at an approximate 10-foot on-center spacing. Alternatively, 4-inch diameter holes at an approximate 20-foot on-center spacing can be used for this type of drainage system. In addition, the weep holes should include a 2 cubic foot pocket of open graded gravel, surrounded by an approved geotextile fabric, at each weep hole location.

- A 4-inch diameter perforated pipe surrounded by 2 cubic feet of gravel per linear foot of drain placed behind the wall, above the retaining wall footing. The gravel layer should be wrapped in a suitable geotextile fabric to reduce the potential for migration of fines. The footing drain should be extended to daylight or tied into a storm drainage system. The actual design of this type of system should be determined by the civil engineer to verify that the drainage system possesses the adequate capacity and slope for its intended use.

## **6.8 Pavement Design Parameters**

Site preparation in the pavement area should be completed as previously recommended in the ***Site Grading Recommendations*** section of this report. The subsequent pavement recommendations assume proper drainage and construction monitoring, and are based on either PCA or CALTRANS design parameters for a twenty (20) year design period. However, these designs also assume a routine pavement maintenance program to obtain the anticipated 20-year pavement service life.

### Pavement Subgrades

It is anticipated that the new pavements will be primarily supported on a layer of compacted structural fill, consisting of scarified, thoroughly moisture conditioned and recompacted existing soils. The near-surface soils generally consist of silty sands, sands, and sandy silts with occasional clayey sands and sandy clays. Based on the results of R-value testing, representative samples of the near surface possess R-values of 65 and 68. Based on the lack of a grading plan and the variability of the composition of the near-surface soils, including the presence of sandy clay layers, we expect that some of the near-surface soils may possess varying pavement support characteristics. Therefore, the subsequent pavement design is based upon a more conservative R-value of 40. Any fill material imported to the site should have support characteristics equal to or greater than that of the on-site soils and be placed and compacted under engineering-controlled conditions. It is recommended that additional R-value testing be performed after completion of rough grading. Depending upon the results of the R-value testing, it may be feasible to use thinner pavement sections in some areas of the site.

### Asphaltic Concrete

Presented below are the recommended thicknesses for new flexible pavement structures consisting of asphaltic concrete over a granular base. The pavement designs are based on the traffic indices (TI's) indicated. The client and/or civil engineer should verify that these TI's are representative of the anticipated traffic volumes. If the client and/or civil engineer determine that the expected traffic volume will exceed the applicable traffic index, we should be contacted for supplementary recommendations. The design traffic indices equate to the following approximate daily traffic volumes over a 20-year design life, assuming six operational traffic days per week.

Traffic Index	No. of Heavy Trucks per Day
4.0	0
5.0	1
6.0	3
7.0	11
8.0	35
9.0	93

For the purpose of the traffic volumes indicated above, a truck is defined as a 5-axle tractor trailer unit with one 8-kip axle and two 32-kip tandem axles. All of the traffic indices allow for 1,000 automobiles per day.

ASPHALT PAVEMENTS (R=40)					
Materials	Thickness (inches)				
	Auto Parking and Auto Drive Lanes (TI = 4.0 to 5.0)	Truck Traffic			
		TI = 6.0	TI = 7.0	TI = 8.0	TI = 9.0
Asphalt Concrete	3	3½	4	5	5½
Aggregate Base	4	6	7	8	10
Compacted Subgrade	12	12	12	12	12

The aggregate base course should be compacted to at least 95 percent of the ASTM D-1557 maximum dry density. The asphaltic concrete should be compacted to at least 95 percent of the Marshall maximum density, as determined by ASTM D-2726. The aggregate base course may consist of crushed aggregate base (CAB) or crushed miscellaneous base (CMB), which is a recycled gravel, asphalt and concrete material. The gradation, R-Value, Sand Equivalent, and Percentage Wear of the CAB or CMB should comply with appropriate specifications contained in the current edition of the "Greenbook" Standard Specifications for Public Works Construction.

#### Portland Cement Concrete

The preparation of the subgrade soils within concrete pavement areas should be performed as previously described for proposed asphalt pavement areas. The minimum recommended thicknesses for the Portland Cement Concrete pavement sections are as follows:

<b>PORTLAND CEMENT CONCRETE PAVEMENTS (R=40)</b>				
<b>Materials</b>	<b>Thickness (inches)</b>			
	Autos and Light Truck Traffic (TI = 6.0)	Truck Traffic		
		TI = 7.0	TI = 8.0	TI = 9.0
PCC	5	5½	6½	8
Compacted Subgrade (95% minimum compaction)	12	12	12	12

The concrete should have a 28-day compressive strength of at least 3,000 psi. Any reinforcement within the PCC pavements should be determined by the project structural engineer. The maximum joint spacing within all of the PCC pavements is recommended to be equal to or less than 30 times the pavement thickness.

## 7.0 GENERAL COMMENTS

---


This report has been prepared as an instrument of service for use by the client, in order to aid in the evaluation of this property and to assist the architects and engineers in the design and preparation of the project plans and specifications. This report may be provided to the contractor(s) and other design consultants to disclose information relative to the project. However, this report is not intended to be utilized as a specification in and of itself, without appropriate interpretation by the project architect, civil engineer, and/or structural engineer. The reproduction and distribution of this report must be authorized by the client and Southern California Geotechnical, Inc. Furthermore, any reliance on this report by an unauthorized third party is at such party's sole risk, and we accept no responsibility for damage or loss which may occur. The client(s)' reliance upon this report is subject to the Engineering Services Agreement, incorporated into our proposal for this project.

The analysis of this site was based on a subsurface profile interpolated from limited discrete soil samples. While the materials encountered in the project area are considered to be representative of the total area, some variations should be expected between boring locations and sample depths. If the conditions encountered during construction vary significantly from those detailed herein, we should be contacted immediately to determine if the conditions alter the recommendations contained herein.

This report has been based on assumed or provided characteristics of the proposed development. It is recommended that the owner, client, architect, structural engineer, and civil engineer carefully review these assumptions to ensure that they are consistent with the characteristics of the proposed development. If discrepancies exist, they should be brought to our attention to verify that they do not affect the conclusions and recommendations contained herein. We also recommend that the project plans and specifications be submitted to our office for review to verify that our recommendations have been correctly interpreted.

The analysis, conclusions, and recommendations contained within this report have been promulgated in accordance with generally accepted professional geotechnical engineering practice. No other warranty is implied or expressed.

# APPENDIX A



SOURCE: USGS TOPOGRAPHIC MAPS OF THE APPLE VALLEY  
 NORTH QUADRANGLE, SAN BERNARDINO COUNTY,  
 CALIFORNIA, 2021.



<b>SITE LOCATION MAP</b>	
PROPOSED APPLE VALLEY ASSEMBLAGE	
APPLE VALLEY, CALIFORNIA	
SCALE: 1" = 2000'	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>
DRAWN: ME	
CHKD: DN	
SCG PROJECT 22G153-1	
<b>PLATE 1</b>	











**GEOTECHNICAL LEGEND**

APPROXIMATE BORING LOCATION

<b>BORING LOCATION PLAN</b>	
PROPOSED APPLE VALLEY ASSEMBLAGE	
APPLE VALLEY, CALIFORNIA	
SCALE: 1" = 350'	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>
DRAWN: ME	
CHKD: DN	
SCG PROJECT 22G153-1	
<b>PLATE 2</b>	

# APPENDIX B

# BORING LOG LEGEND

SAMPLE TYPE	GRAPHICAL SYMBOL	SAMPLE DESCRIPTION
AUGER		SAMPLE COLLECTED FROM AUGER CUTTINGS, NO FIELD MEASUREMENT OF SOIL STRENGTH. (DISTURBED)
CORE		ROCK CORE SAMPLE: TYPICALLY TAKEN WITH A DIAMOND-TIPPED CORE BARREL. TYPICALLY USED ONLY IN HIGHLY CONSOLIDATED BEDROCK.
GRAB		SOIL SAMPLE TAKEN WITH NO SPECIALIZED EQUIPMENT, SUCH AS FROM A STOCKPILE OR THE GROUND SURFACE. (DISTURBED)
CS		CALIFORNIA SAMPLER: 2-1/2 INCH I.D. SPLIT BARREL SAMPLER, LINED WITH 1-INCH HIGH BRASS RINGS. DRIVEN WITH SPT HAMMER. (RELATIVELY UNDISTURBED)
NSR		NO RECOVERY: THE SAMPLING ATTEMPT DID NOT RESULT IN RECOVERY OF ANY SIGNIFICANT SOIL OR ROCK MATERIAL.
SPT		STANDARD PENETRATION TEST: SAMPLER IS A 1.4 INCH INSIDE DIAMETER SPLIT BARREL, DRIVEN 18 INCHES WITH THE SPT HAMMER. (DISTURBED)
SH		SHELBY TUBE: TAKEN WITH A THIN WALL SAMPLE TUBE, PUSHED INTO THE SOIL AND THEN EXTRACTED. (UNDISTURBED)
VANE		VANE SHEAR TEST: SOIL STRENGTH OBTAINED USING A 4 BLADED SHEAR DEVICE. TYPICALLY USED IN SOFT CLAYS-NO SAMPLE RECOVERED.

## COLUMN DESCRIPTIONS

### DEPTH:

Distance in feet below the ground surface.

### SAMPLE:

Sample Type as depicted above.

### BLOW COUNT:

Number of blows required to advance the sampler 12 inches using a 140 lb hammer with a 30-inch drop. 50/3" indicates penetration refusal (>50 blows) at 3 inches. WH indicates that the weight of the hammer was sufficient to push the sampler 6 inches or more.

### POCKET PEN.:

Approximate shear strength of a cohesive soil sample as measured by pocket penetrometer.

### GRAPHIC LOG:

Graphic Soil Symbol as depicted on the following page.

### DRY DENSITY:

Dry density of an undisturbed or relatively undisturbed sample in lbs/ft<sup>3</sup>.

### MOISTURE CONTENT:

Moisture content of a soil sample, expressed as a percentage of the dry weight.

### LIQUID LIMIT:

The moisture content above which a soil behaves as a liquid.

### PLASTIC LIMIT:

The moisture content above which a soil behaves as a plastic.

### PASSING #200 SIEVE:

The percentage of the sample finer than the #200 standard sieve.

### UNCONFINED SHEAR:

The shear strength of a cohesive soil sample, as measured in the unconfined state.

# SOIL CLASSIFICATION CHART

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS	
			GRAPH	LETTER		
<p><b>COARSE GRAINED SOILS</b></p> <p>MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE</p>	<p><b>GRAVEL AND GRAVELLY SOILS</b></p>	<p>CLEAN GRAVELS</p> <p>(LITTLE OR NO FINES)</p>		<b>GW</b>	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES	
		<p>GRAVELS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		<b>GP</b>	POORLY-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES	
		<p>MORE THAN 50% OF COARSE FRACTION RETAINED ON NO. 4 SIEVE</p>	<p>CLEAN SANDS</p> <p>(LITTLE OR NO FINES)</p>		<b>SW</b>	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
			<p>SANDS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		<b>SP</b>	POORLY-GRADED SANDS, GRAVELLY SAND, LITTLE OR NO FINES
	<p>MORE THAN 50% OF COARSE FRACTION PASSING ON NO. 4 SIEVE</p>	<p><b>SAND AND SANDY SOILS</b></p>	<p>CLEAN SANDS</p> <p>(LITTLE OR NO FINES)</p>		<b>SM</b>	SILTY SANDS, SAND - SILT MIXTURES
			<p>SANDS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		<b>SC</b>	CLAYEY SANDS, SAND - CLAY MIXTURES
	<p><b>FINE GRAINED SOILS</b></p> <p>MORE THAN 50% OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE</p>	<p><b>SILTS AND CLAYS</b></p>	<p>LIQUID LIMIT LESS THAN 50</p>		<b>ML</b>	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
					<b>CL</b>	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
					<b>OL</b>	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
		<p><b>SILTS AND CLAYS</b></p>	<p>LIQUID LIMIT GREATER THAN 50</p>		<b>MH</b>	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS
				<b>CH</b>	INORGANIC CLAYS OF HIGH PLASTICITY	
				<b>OH</b>	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS	
<p><b>HIGHLY ORGANIC SOILS</b></p>				<b>PT</b>	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS	

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 18 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				ALLUVIUM: Brown fine to coarse Sandy Silt to Silty fine to coarse Sand, medium dense-dry	117	1						
				OLDER ALLUVIUM: Orange Brown fine to coarse Sandy Silt, little Clay, very dense-dry	116	2						
5		44		Red Brown Silty fine to coarse Sand, medium dense-dry	109	2						
				Light Brown fine Sandy Silt, some Clay, little Calcareous nodules/veining, slightly cemented, slightly porous, very dense-dry	104	2						
10		50/6"		Light Brown fine to coarse Sandy Silt, very dense-damp	111	5						
15						4						
20						5						
25		54		Light Brown Silty fine to coarse Sand, very dense-damp		5						
30						4						
Boring Terminated at 30'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 16 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
			3.5	[Hatched Pattern]	OLDER ALLUVIUM: Light Brown fine to coarse Sandy Clay, little Silt, cemented, very stiff-damp		5					
5				[Dotted Pattern]	Light Red Brown fine Sandy Silt, trace to little medium to coarse Sand, medium dense-damp		4					
				[Dotted Pattern]	Gray Brown fine to coarse Sandy Silt, medium dense-damp		2					
10				[Dotted Pattern]	Light Red Brown fine Sandy Silt, little Clay, little medium to coarse Sand, cemented, little Calcareous nodules, dense-damp to moist		9					
15				[Dotted Pattern]	@ 13½ feet, very dense		4					
20				[Dotted Pattern]	Light Red Brown fine to coarse Sandy Silt, little Clay, cemented, very dense-damp		4					
Boring Terminated at 20'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 11.5 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
	X	31			ALLUVIUM: Light Red Brown fine to coarse Sandy Silt, medium dense-dry	119	1					
	X	44			Light Red Brown Silty fine to medium Sand to fine to medium Sandy Silt, little Calcareous veins, medium dense-damp	112	3					
5	X	19			Light Red Brown Silty fine to coarse Sand, medium dense-dry	106	2					
	X	40			Light Red Brown fine to medium Sandy Silt, trace coarse Sand, trace fine root fibers, medium dense-dry	116	1					
10	X	48			OLDER ALLUVIUM: Red Brown fine Sandy Silt, trace to little Clay, little Calcareous nodules, trace fine root fibers, dense-damp	113	3					
	X	64					104	5				
15					Boring Terminated at 15'							

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 18 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
5		30			ALLUVIUM: Brown fine to coarse Sandy Silt, trace Clay, trace fine root fibers, dense-dry		2					
		35			OLDER ALLUVIUM: Red Brown fine to medium Sandy Clay, little Silt, cemented, hard-damp		2					
		32	3.5		@ 8½ feet, slightly porous		4					
10		75/10"	3.5		Light Red Brown fine Sandy Clay, some Silt, weakly cemented, hard-damp		5					
15		70/10"	4.0		Light Brown fine to medium Sandy Silt, trace coarse Sand, trace Calcareous nodules, weakly cemented, very dense-damp		6					
20		50/6"				3						
Boring Terminated at 20'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1      DRILLING DATE: 3/30/22      WATER DEPTH: Dry  
 PROJECT: Apple Valley Assemblage      DRILLING METHOD: Hollow Stem Auger      CAVE DEPTH: 17 feet  
 LOCATION: Apple Valley, California      LOGGED BY: Joey Hernandez      READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS	
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)		
SURFACE ELEVATION: --- MSL													
		29			ALLUVIUM: Light Brown fine to coarse Sandy Silt, trace fine root fibers, medium dense-dry	117	1						
		33					112	2					
5		27			Orange Brown Silty fine to coarse Sand, medium dense-dry	108	1						
		50/6"			OLDER ALLUVIUM: Light Brown fine to medium Sandy Clay, trace coarse Sand, slightly porous, weakly cemented, hard-damp	112	3						
10		50/6"			Light Brown fine to medium Sandy Silt, trace coarse Sand, little Calcareous nodules/veining, very dense-moist		7					Disturbed Sample	
15		24			Light Brown fine to coarse Sandy Silt, slightly cemented, medium dense to very dense-dry	111	2						
20		67/10"					117	2					
25		50/11"										@ 24', No Sample Recovery	
Boring Terminated at 25'													

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1      DRILLING DATE: 3/29/22      WATER DEPTH: Dry  
 PROJECT: Apple Valley Assemblage      DRILLING METHOD: Hollow Stem Auger      CAVE DEPTH: 21 feet  
 LOCATION: Apple Valley, California      LOGGED BY: Joey Hernandez      READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
					SURFACE ELEVATION: --- MSL							
					ALLUVIUM: Light Brown fine to coarse Sandy Silt, loose-dry	108	1					
		13										
		30			Light Red Brown Silty fine to coarse Sand to fine to coarse Sandy Silt, medium dense-damp		2					@ 3', Disturbed Sample
5		46	4.0		OLDER ALLUVIUM: Red Brown to Brown fine Sandy Clay, little Silt, trace medium Sand, trace fine root fibers, slightly porous, slightly cemented, dense-damp to moist	108	7					
		63			Light Red Brown fine to medium Sandy Silt, trace coarse Sand, trace Calcareous nodules, dense-damp	110	5					
10		67			@ 9 to 15 feet, little Clay, weakly cemented	109	4					
		55				105	4					
15		67				114	2					
20		50/5"			Light Brown fine to medium Sandy Clay, little Silt, weakly cemented, very dense-damp	100	5					
25		50/5"			Light Brown fine to medium Sandy Silt, trace coarse Sand, very dense-damp	100	3					
30					Boring Terminated at 30'							

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 17 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS	
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)		
SURFACE ELEVATION: --- MSL													
5		19			OLDER ALLUVIUM: Gray Brown fine to medium Sandy Silt, little Clay, trace coarse Sand, medium dense to very dense-dry to damp		3						
		31											
		88/6"											
10		76				Light Red Brown fine Sandy Silt, trace medium to coarse Sand, very dense-damp		4					
15		71/11"	3.5			Red Brown fine Sandy Clay, trace coarse Sand, cemented, hard-damp		5					
20		70/11"	1.0										
25		72			Brown Silty fine to coarse Sand, trace fine Gravel, very dense-dry		2						
Boring Terminated at 25'													

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1      DRILLING DATE: 3/29/22      WATER DEPTH: Dry  
 PROJECT: Apple Valley Assemblage      DRILLING METHOD: Hollow Stem Auger      CAVE DEPTH: 10.3 feet  
 LOCATION: Apple Valley, California      LOGGED BY: Joey Hernandez      READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		17			ALLUVIUM: Light Brown Silty fine to coarse Sand, medium dense-dry	108	1					
		78			OLDER ALLUVIUM: Light Red Brown fine Sandy Silt, trace medium to coarse Sand, slightly porous, cemented, little Calcareous nodules, very dense-damp	116	4					
5		32			Light Red Brown Silty fine to coarse Sand, medium dense to dense-dry	118	1					
		48						1				@ 7', Disturbed Sample
10		60			Brown fine to medium Sandy Silt, trace coarse Sand, weakly cemented, dense-damp	114	3					
		80			Red Brown fine Sandy Silt, trace medium to coarse Sand, weakly cemented, very dense-damp	109	5					
15					Boring Terminated at 15'							

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 11 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
9				2.0	ALLUVIUM: Light Brown fine to medium Sandy Silt, trace coarse Sand, trace fine root fibers, loose-damp		2					
45					Light Red Brown fine Sandy Silt, little medium to coarse Sand, trace Calcareous nodules, weakly cemented, dense-damp		3					
49					Light Brown fine to coarse Sandy Silt, dense-damp		4					
50					Light Brown fine to medium Sandy Silt, trace coarse Sand, slightly cemented, very dense-damp		4					
58					Light Brown fine to medium Sandy Clay, little Silt, trace coarse Sand, hard-damp		5					
46					Light Brown fine to medium Sandy Silt, trace Clay, trace medium Sand, trace fine Gravel, dense-damp		3					
20					Boring Terminated at 20'							

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 13.5 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				ALLUVIUM: Brown fine to coarse Sandy Silt, loose-dry		2						
5		5		OLDER ALLUVIUM: Gray Brown fine Sandy Silt, little medium to coarse Sand, little Clay, slightly cemented, medium dense to dense-damp		4						
5		39										
		21				3						
10		85/11"		Brown fine to medium Sandy Silt, little Clay, trace coarse Sand, very dense-moist		8						
15		70/10"	3.0	Red Brown fine Sandy Clay, some Silt, little medium to coarse Sand, hard-damp		6						
20		85/6"		Light Red Brown fine to medium Sandy Silt, trace coarse Sand, very dense-damp		4						
Boring Terminated at 20'												

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 11 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
	X	11			ALLUVIUM: Brown fine to coarse Sandy Silt, little fine Root Fibers, loose-dry	107	2					
	X	63			OLDER ALLUVIUM: Red Brown Silty fine to coarse Sand, dense-dry	119	2					
5	X	50/6"			Brown fine to medium Sandy Silt, trace coarse Sand, very dense-damp	3						@ 5', Disturbed Sample
	X	50/5"			@ 7 feet, little Clay	108	3					
10	X	50/5"			Brown fine Sandy Clay, little Silt, little medium to coarse Sand, weakly cemented, trace Calcareous veins, very dense-dry to damp	114	3					
	X	70/6"			Light Brown fine to medium Sandy Silt, trace coarse Sand, very dense-damp	4						
15					Boring Terminated at 15'							

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 22 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				ALLUVIUM: Light Brown fine to medium Sandy Silt, trace coarse Sand, medium dense-dry		2						
				OLDER ALLUVIUM: Light Red Brown fine to coarse Sandy Silt, some Clay, weakly cemented, medium dense-damp		4						
5		13		Red Brown fine Sandy Silt, trace medium to coarse Sand, medium dense-damp		4						
		25		Light Red Brown fine to medium Sandy Silt, dense-dry		2						
		29		Light Red Brown fine to medium Sandy Clay, little to some Silt, little Calcareous nodules/veining, weakly cemented, hard-damp		5						
10		42		Light Red Brown fine to medium Sandy Clay, little to some Silt, little Calcareous nodules/veining, weakly cemented, hard-damp		5						
		56	4.5	Light Brown fine to medium Sandy Silt, trace coarse Sand, dense-damp		3						
15		52										
		41										
20												
25				Boring Terminated at 25'								

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 25 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		10			<u>ALLUVIUM</u> : Brown fine Sandy Silt, trace fine Root Fibers, little medium to coarse Sand, loose-dry	108	1					@ 3', Disturbed Sample
		29			<u>OLDER ALLUVIUM</u> : Brown Silty fine to coarse Sand, medium dense-dry		1					
5		40			Orange Brown Silty fine to coarse Sand to fine to coarse Sandy Silt, trace fine Gravel, slightly porous, weakly cemented, medium dense-dry	117	2					
		85/10"			Red Brown fine to medium Sandy Silt, trace coarse Sand, little Clay, weakly cemented, trace Calcareous veins, dense to very dense-dry to damp	122	7					
10		71/11"				122	2					
15		30					4					
20		10				Light Brown fine Sandy Silt, little fine to coarse Sand, medium dense-damp		3				
25		67/11"				Light Brown fine to medium Sandy Silt, trace coarse Sand, very dense-damp		4				
30		63/6"				Light Brown fine Sandy Silt, trace medium to coarse Sand, very dense-damp		3				
Boring Terminated at 30'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 23.5 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				ALLUVIUM: Brown fine to coarse Sandy Silt, little fine Root Fibers, loose-dry		1						@ 1', Disturbed Sample
				Light Red Brown fine to coarse Sand, trace Silt, trace fine to coarse Gravel, medium dense-dry	106	1						
5		20		Orange Brown fine to coarse Sandy Silt, some Clay, little Calcareous nodules, weakly cemented, dense to very dense-damp		1						@ 5', Disturbed Sample
				Orange Brown fine to coarse Sandy Silt, some Clay, little Calcareous nodules, weakly cemented, dense to very dense-damp		7						@ 7', Disturbed Sample
10		54		Orange Brown fine to coarse Sandy Silt, some Clay, little Calcareous nodules, weakly cemented, dense to very dense-damp	104	4						
				Orange Brown fine to coarse Sandy Silt, some Clay, little Calcareous nodules, weakly cemented, dense to very dense-damp		4						@ 14', Disturbed Sample
15		50/5"		Red Brown Silty fine to coarse Sand, very dense-damp		4						
				Red Brown Silty fine to coarse Sand, very dense-damp	99	5						
20		50/5"		Red Brown Silty fine to coarse Sand, very dense-damp		5						
				Red Brown fine to coarse Sandy Silt, trace Clay, little Calcareous nodules/veining, cemented, very dense-damp	106	2						
25		50/5"		Red Brown fine to coarse Sandy Silt, trace Clay, little Calcareous nodules/veining, cemented, very dense-damp		2						
				Red Brown Silty fine to coarse Sand. trace to little Clay, weakly cemented, very dense-damp		3						@ 29', Disturbed Sample
30		50/4"		Red Brown Silty fine to coarse Sand. trace to little Clay, weakly cemented, very dense-damp		3						
Boring Terminated at 30'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 18.5 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		8			ALLUVIUM: Light Brown Silty fine to coarse Sand, loose to medium dense-dry to damp		2					
		15			@ 3½', trace to little Clay		2					
5		25					2					
		75/6"			OLDER ALLUVIUM: Red Brown Silty fine to medium Sand, trace coarse Sand, trace fine Gravel, very dense-damp		5					
10					Brown fine to coarse Sandy Clay, little Silt, cemented, hard-damp		7					
15		63					7					
		79/5"			@ 18½ feet, some Calcareous nodules		7					
20						5						
		85/9"										
25					Boring Terminated at 25'							

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 7 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		10			ALLUVIUM: Light Red Brown fine to coarse Sandy Silt, medium dense-damp		2					
		58			OLDER ALLUVIUM: Brown fine to coarse Sandy Silt, little to some Clay, cemented, very dense-damp		4					
5		43			Light Red Brown fine Sandy Silt, trace medium to coarse Sand, dense-damp		3					
		85/5"			Light Red Brown fine to medium Sandy Silt, little Clay, little Calcareous nodules/veining, cemented, very dense-damp		5					
10		75/11"					3					
15					Boring Terminated at 15'							

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 19 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)		GRAPHIC LOG	DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	
SURFACE ELEVATION: --- MSL											
		9		[Symbol]	<u>ALLUVIUM</u> : Light Brown fine to medium Sandy Silt, trace coarse Sand, little fine Root Fibers, loose-dry to damp		2				
		38		[Symbol]	<u>OLDER ALLUVIUM</u> : Light Brown fine to coarse Sandy Silt, trace to little Clay, dense to very dense-damp		3				
5				[Symbol]			3				
		50/6"		[Symbol]							
				[Symbol]			6				
10				[Symbol]							
		95/10"		[Symbol]							
				[Symbol]							
15				[Symbol]			5				
		45		[Symbol]							
				[Symbol]							
20				[Symbol]	Light Red Brown fine to medium Sandy Silt, trace Clay, trace coarse Sand, cemented, very dense-damp		7				
		104/9"		[Symbol]							
Boring Terminated at 20'											

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 4/1/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 20 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)		GRAPHIC LOG	DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	
SURFACE ELEVATION: --- MSL											
		15		ALLUVIUM: Brown fine to coarse Sandy Silt, trace fine Root Fibers, medium dense to dense-dry	89	1					
		66		@ 3 feet, slightly cemented	108	2					
5		53		OLDER ALLUVIUM: Brown to Red Brown Clayey fine to coarse Sand, little Silt, dense to very dense-damp	120	3					
		50/5"		@ 7 feet, some Calcareous veining	108	3					
10		60		Gray Brown Silty fine to coarse Sand, trace Calcareous nodules/veining, cemented, dense to very dense-dry to damp	109	3					
15		40		@ 13½ feet, trace to little Clay		5					
20		71/11"				2					
25		58		Light Red Brown fine Sandy Silt, little medium to coarse Sand, dense-damp		3					
30		54				5					
Boring Terminated at 30'											

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 4/1/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 15 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				ALLUVIUM: Red Brown fine to coarse Sandy Silt, little fine Gravel, trace fine Root Fibers, medium dense-dry	95	1						
				Light Red Brown fine to coarse Sandy Silt, little to some Clay, medium dense-damp	112	2						
5		50/5"		OLDER ALLUVIUM: Light Red Brown fine to coarse Sandy Silt, trace fine Gravel, little Calcareous nodules, dense to very dense-damp	107	3						
		50/5"				3					@ 7', Disturbed Sample	
10		52			107	3						
15		58	4.5	Red Brown fine to medium Sandy Clay, little Silt, trace Calcareous nodules, hard-damp		4						
20		63				5						
Boring Terminated at 20'												

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1      DRILLING DATE: 4/1/22      WATER DEPTH: Dry  
 PROJECT: Apple Valley Assemblage      DRILLING METHOD: Hollow Stem Auger      CAVE DEPTH: 17 feet  
 LOCATION: Apple Valley, California      LOGGED BY: Michelle Esparza      READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS	
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)		
SURFACE ELEVATION: --- MSL													
					ALLUVIUM: Light Red Brown fine to coarse Sandy Silt, medium dense-dry to damp	111	1						
		15					113	2					
		18				OLDER ALLUVIUM: Light Red Brown fine to coarse Sandy Silt, little Clay, cemented, little Calcareous nodules/veining, very dense-dry	119	2					
5		75/11"				Light Red Brown fine to coarse Sandy Silt, little Clay, cemented, little Calcareous veining, dense to very dense-damp	105	3					
		50/5"					112	6					
10		56											
		45				Light Red Brown fine to medium Sandy Silt, little Clay, little coarse Sand, dense-damp		3					
15													
		40			Red Brown fine Sandy Silt, little medium Sand, dense-dry		2						
20													
		34			Light Gray Brown fine to medium Sandy Silt, trace coarse Sand, dense-dry		2						
25													
Boring Terminated at 25'													

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 19 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				OLDER ALLUVIUM: Light Red Brown fine to medium Sandy Silt, fine trace Gravel, trace fine Root Fibers, dense-dry		2						
		72/11"		Gray Brown fine Sandy Silt, trace medium Sand, trace fine Root Fibers, very dense-dry		1						
5			2.5	Gray Brown fine to medium Sandy Clay, little Silt, weakly cemented, very dense-damp		4						
			4.5			4						
				Light Red Brown Silty fine to coarse Sand, dense-dry		2						
10						2						
				Light Red Brown fine to medium Sandy Silt, trace coarse Sand, trace Clay, slightly cemented, very dense-damp		3						
15						3						
						3						
20						3						
						3						
25						3						
Boring Terminated at 25'												

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 12 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
	X	26			OLDER ALLUVIUM: Brown fine Sandy Silt, trace medium Sand, trace fine Root Fibers, weakly cemented, medium dense-dry	116	1					
	X	50/5"			Light Red Brown fine Sandy Silt, weakly cemented, very dense-dry to damp	94	2					
5	X	50/5"			Light Red Brown fine to medium Sandy Silt, weakly cemented, trace Calcareous nodules, very dense-dry	113	1					
	X	50/5"			@ 7 to 8 feet, little Clay	113	1					
10	X	85/5"			@ 9-15 feet, damp	112	6					
	X	65/5"					4					
15					Boring Terminated at 15'							

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 21 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				ALLUVIUM: Light Red Brown Silty fine to coarse Sand to fine to coarse Sandy Silt, trace fine Root Fibers, loose-dry		1					@ 1', Disturbed Sample	
				OLDER ALLUVIUM: Light Red Brown fine to coarse Sandy Silt, little Clay, little fine Gravel, cemented, medium dense-dry	114	2					@ 3', Disturbed Sample	
				Light Red Brown fine to coarse Sandy Silt, trace fine Gravel, very dense-dry to damp		2					@ 7', Disturbed Sample	
				@ 9 feet, slightly porous, cemented		3					@ 9', Disturbed Sample	
				Light Red Brown fine to medium Sandy Silt, little to some Clay, trace coarse Sand, little Calcareous nodules, dense-damp		5						
				Light Red Brown fine to medium Sandy Clay, little Silt, trace coarse Sand, slightly cemented, hard-damp		4						
				Light Gray Brown fine to medium Sandy Silt, trace coarse Sand, trace Clay, little Calcareous nodules, dense-damp		5						
				Boring Terminated at 30'								

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 15 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		11		ALLUVIUM: Brown fine Sandy Silt, little medium to coarse Sand, medium dense-dry		1						
		16		Red Gray Brown Silty fine to medium Sand, trace coarse Sand, medium dense-dry		2						
5		80/5"		OLDER ALLUVIUM: Light Red Brown Silty fine to coarse Sand, weakly cemented, very dense-damp		3						
		87/4"		@ 8½ feet, little Clay		3						
10												
		63/11"		Light Red Brown fine to coarse Sandy Silt, cemented, trace Calcareous veining, very dense-damp		3						
15												
		50/6"		@ 18½ feet, trace to little Clay		5						
20												
Boring Terminated at 20'												

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 4/1/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 12 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		10			ALLUVIUM: Brown fine to medium Sandy Silt, trace coarse Sand, trace fine Root Fibers, medium dense-dry		1					
		15			OLDER ALLUVIUM: Light Red Brown fine to medium Sandy Silt, little Clay, trace fine Gravel, cemented, medium dense-damp		3					
5		25			Light Red Brown fine to medium Sandy Clay, trace coarse Sand, cemented, medium stiff to very stiff-damp		4					
		75/5"	3.0		@ 8½ to 20 feet, trace Calcareous nodules/veining		5					
10		50/4"	4.0				5					
15		50/4"	4.5				7					
20					Boring Terminated at 20'							

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 4/1/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 21 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				ALLUVIUM: Brown fine to medium Sandy Silt, trace coarse Sand, trace fine Root Fibers, medium dense-dry		1						
5		11		15		2						
				OLDER ALLUVIUM: Light Red Brown fine to medium Sandy Silt, little Clay, trace coarse Sand, dense-dry		2						
				Light Red Brown fine to medium Sandy Silt, trace coarse Sand, little Calcareous nodules/veining, weakly cemented, very dense-damp		7						
10				Light Red Brown fine to medium Sandy Clay, trace coarse Sand, little Calcareous nodules, weakly cemented, hard-damp		7						
				Light Red Brown fine to medium Sandy Silt, little Calcareous nodules, weakly cemented, very dense-damp		4						
15				Light Red Brown fine to medium Sandy Silt, little Calcareous nodules, weakly cemented, very dense-damp		6						
				Boring Terminated at 25'								

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1      DRILLING DATE: 3/31/22      WATER DEPTH: Dry  
 PROJECT: Apple Valley Assemblage      DRILLING METHOD: Hollow Stem Auger      CAVE DEPTH: 23 feet  
 LOCATION: Apple Valley, California      LOGGED BY: Michelle Esparza      READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
					ALLUVIUM: Brown fine to medium Sandy Silt, medium dense to dense-dry	117	1					
						117	1					
5		28										
		31										
		50/6"	4.0		OLDER ALLUVIUM: Red Brown fine to medium Sandy Clay, some Silt, little Calcareous nodules, weakly cemented, hard-dry to damp	112	2					
		87/9"	3.5			113	3					
10		50/5"			Gray Brown fine Sandy Silt, little medium Sand, weakly cemented, very dense-damp	106	3					
15		50/5"			Gray Brown fine to medium Sandy Silt, very dense-damp	107	4					
20		50/5"				110	3					
25		50/5"			Red Brown to Brown fine to medium Sandy Clay, some Silt, little Calcareous nodules, weakly cemented, hard-damp	102	3					
30		50/5"										
Boring Terminated at 30'												@ 29', No Sample Recovery

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1      DRILLING DATE: 3/30/22      WATER DEPTH: Dry  
 PROJECT: Apple Valley Assemblage      DRILLING METHOD: Hollow Stem Auger      CAVE DEPTH: 23 feet  
 LOCATION: Apple Valley, California      LOGGED BY: Michelle Esparza      READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				[Symbol]	ALLUVIUM: Brown fine to medium Sandy Silt, trace coarse Sand, little fine Gravel, trace fine Root Fibers, medium dense-dry	123	1					
				[Symbol]	OLDER ALLUVIUM: Brown Silty fine to medium Sand, weakly cemented, very dense-dry	114	2					
5				[Symbol]	Red Brown fine to medium Sandy Clay, little coarse Sand, weakly cemented, hard-dry		2					@ 5', Disturbed Sample
				[Symbol]	Brown fine to medium Sandy Silt, little coarse Sand, trace fine Root Fibers, very dense-dry to damp	117	6					
10				[Symbol]		113	2					
				[Symbol]	@ 13½ feet, little to some Calcareous veining	108	3					
20				[Symbol]	Gray Brown fine Sandy Silt, trace medium to coarse Sand, very dense-dry	108	2					
25				[Symbol]	Gray Brown fine to medium Sandy Silt, trace coarse Sand, very dense-damp		3					@ 24', Disturbed Sample
30				[Symbol]	@ 29 feet, little to some Clay		5					@ 29', Disturbed Sample
Boring Terminated at 30'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 14 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
					ALLUVIUM: Brown fine to medium Sandy Silt, trace coarse Sand, trace fine Root Fibers, medium dense-dry		1					
5		50/5"	3.5		Red Brown fine to medium Sandy Clay, little coarse Sand, trace Calcareous veining, weakly cemented, trace fine Root Fibers, stiff to hard-damp		7					
		65/5"			Gray Brown fine to medium Sandy Silt, trace coarse Sand, very dense-damp		2					
10		50/5"			Red Brown Silty fine to medium Sand, little Clay, very dense-damp		3					
15		50/5"			Red Brown fine to medium Sandy Silt, trace coarse Sand, very dense-dry to damp		3					
20		50/5"					2					
25		50/5"	3.0		Gray Brown fine to medium Sandy Clay, little Silt, weakly cemented, trace Calcareous nodules, very stiff to hard-damp		6					
Boring Terminated at 25'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 7 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)		GRAPHIC LOG	DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	
SURFACE ELEVATION: --- MSL											
		27		[Symbol]	ALLUVIUM: Brown fine to medium Sandy Silt, trace coarse Sand, medium dense-damp		2				
		72/11"		[Symbol]	@ 3½ feet, 2-inch fine to medium Sandy Silt lens		4				
5		48		[Symbol]	OLDER ALLUVIUM: Gray Clayey fine to coarse Sand, little Silt, weakly cemented, very dense-dry to damp		2				
		50/5"		[Symbol]	Brown fine to medium Sandy Silt, little coarse Sand, trace fine to coarse Gravel, dense to very dense-dry to damp		5				
10				[Symbol]	Red Brown fine to medium Sandy Clay, little Silt, weakly cemented, very stiff to hard-damp						
		42		[Symbol]	Brown fine to medium Sandy Silt, trace coarse Sand, trace fine to coarse Gravel, dense-dry		2				
15				[Symbol]	Boring Terminated at 15'						

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 19 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				OLDER ALLUVIUM: Gray Brown fine to medium Sandy Silt, trace coarse Sand, trace fine Root Fibers, dense-dry		2						
		43		Red Brown Clayey fine to medium Sand, little Silt, trace fine Root Fibers, weakly cemented, very dense-damp		3						
5		50/5"		Light Red Brown fine to medium Sandy Silt, trace Clay, very dense-damp		4						
		87/10"		@ 8½ feet, trace coarse Sand		3						
10		50/5"		Red Brown fine to medium Sandy Clay, little Silt, porous, cemented, stiff to hard-damp		3						
		44	2.5	Red Brown fine to medium Sandy Silt, trace Clay, very dense-dry to damp		3						
15		50/5"				3						
20		67				1						
25				Boring Terminated at 25'								

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 13 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
					OLDER ALLUVIUM: Light Red Brown Silty fine to coarse Sand to fine to coarse Sandy Silt, weakly cemented, medium dense-dry	118	2					
					@ 3 feet, little Clay, porous, dense	121	2					
5		50/5"	3.0		Light Red Brown fine Sandy Clay, trace medium coarse sand, trace fine Root Fibers, slightly porous, weakly cemented, hard-damp		4					@ 5' Disturbed Sample
					Light Red Brown fine to medium Sandy Silt, trace Clay, trace coarse Sand, weakly cemented, little Calcareous nodules/veining, very dense-damp		3					@ 7', Disturbed Sample
10		50/5"			Light Red Brown Silty fine to coarse Sand, very dense-dry	108	2					
15		50/5"	4.0		Light Red Brown fine to coarse Sandy Clay, little Silt, weakly cemented, hard-damp		5					
20		50/5"	4.5		Light Red Brown fine Sandy Clay, trace to little medium to coarse Sand, weakly cemented, hard-damp		4					
Boring Terminated at 20'												

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1      DRILLING DATE: 3/29/22      WATER DEPTH: Dry  
 PROJECT: Apple Valley Assemblage      DRILLING METHOD: Hollow Stem Auger      CAVE DEPTH: 20 feet  
 LOCATION: Apple Valley, California      LOGGED BY: Michelle Esparza      READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
					ALLUVIUM: Gray Brown fine to medium Sandy Silt, little Clay, trace coarse Sand, trace fine root fibers, weakly cemented, medium dense-dry	118	1					
					OLDER ALLUVIUM: Gray Brown fine Sandy Clay, weakly cemented, little medium Sand, porous, very stiff to hard-damp	113	3					
5	X	50/5"	3.0		Light Red Brown Clayey fine to medium Sand, little Silt, weakly cemented, very dense-damp		3					@ 5', Disturbed Sample
	X	50/5"			Red Brown fine to medium Sandy Silt, very dense-damp		3					@ 7', Disturbed Sample
10	X	50/5"	4.0		Red Brown fine to coarse Sandy Clay, hard-dry to damp	109	2					
15	X	88	4.5		@ 13½ to 20 feet, weakly cemented		5					
20	X	80/4"	4.0				3					
25	X	48			Red Brown fine to medium Sandy Silt, trace coarse Sand, dense-dry		2					
30	X	80/5"	4.5		Light Red Brown fine Sandy Clay, little medium to coarse Sand, weakly cemented, little Calcareous nodules, hard-damp		7					
Boring Terminated at 30'												

TBL\_22G153-1.GPJ\_SOCALGEO.GDT\_7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 15 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
	X	24			ALLUVIUM: Brown fine Sandy Silt, little medium Sand, trace fine Root Fibers, medium dense-dry		1					@ 1', Disturbed Sample
	X	62	4.5		OLDER ALLUVIUM: Gray Brown fine Sandy Clay, some Silt, trace medium Sand, weakly cemented, hard-dry	121	2					
5	X	50/5"	4.5		@ 5 feet, slightly porous	112	1					
	X	50/5"			Light Red Brown fine to medium Sandy Silt, slightly porous, weakly cemented, very dense-damp		7					@ 7', Disturbed Sample
10	X	50/5"			Red Brown Silty fine to medium Sand, trace coarse Sand, weakly cemented, very dense-damp		3					@ 9', Disturbed Sample
	X	50/5"			Light Red Brown fine to medium Sandy Silt, weakly cemented, very dense-damp		3					
15	X	50/5"			Red Brown fine to coarse Sandy Silt, trace fine Gravel, very dense-dry		2					
20	X	50/5"										
Boring Terminated at 20'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 11 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
				ALLUVIUM: Brown fine to medium Sandy Silt, trace fine Root Fibers, medium dense-dry		1						
		82/9"	4.5	OLDER ALLUVIUM: Red Brown fine to medium Sandy Clay, little Silt, weakly cemented, hard-damp		5						
5				Light Gray Brown fine to medium Sandy Silt, trace coarse Sand, very dense-dry		2						
		61		Red Brown fine to medium Sandy Clay, some Silt, weakly cemented, hard-damp		4						
10			70/9"	Light Red Brown fine to medium Sandy Silt, trace coarse Sand, very dense-dry		2						
				Light Red Brown fine to medium Sandy Silt, trace coarse Sand, very dense-dry		2						
15			87/11"									
20		87				1						
Boring Terminated at 20'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 9 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		15		ALLUVIUM: Light Brown fine to medium Sandy Silt, trace coarse Sand, trace fine Root Fibers, medium dense-damp		2						
		52	4.5	ALLUVIUM: Gray Brown fine to medium Sandy Clay, little coarse Sand, hard-damp		3						
5		37		Light Red Brown fine to medium Sandy Silt, trace coarse Sand, dense-dry to damp		2						
		50/5"		@ 8½ to 15 feet, little Clay, very dense		3						
10												
		74/11"				2						
15					Boring Terminated at 15'							

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 19 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		13			ALLUVIUM: Brown Silty fine to coarse Sand, trace fine Root Fibers, medium dense-dry		1					
		50/5"			ALLUVIUM: Gray Brown fine to medium Sandy Silt, weakly cemented, very dense-dry to damp		2					
5		72/5"					5					
		87	3.5		Gray Brown fine Sandy Clay, little Silt, little medium to coarse Sand, hard-damp		3					
10												
		30			Gray Brown Silty fine to medium Sand, trace to little coarse Sand, cemented, dense-dry		1					
15												
		50/5"			Gray Brown fine to medium Sandy Silt, trace to little Clay, weakly cemented, very dense-damp		3					
20												
		65/5"					5					
25												
Boring Terminated at 25'												

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 20 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
16	✕	16		ALLUVIUM: Light Brown Silty fine to coarse Sand, trace fine Root Fibers, medium dense-dry	114	1						
15	✕	15					1					@ 3', Disturbed Sample
5	✕	50/5"		OLDER ALLUVIUM: Red Brown Clayey fine to coarse Sand, cemented, very dense-dry		1						@ 5', Disturbed Sample
	✕	50/5"				109	3					
10	✕	50/5"		Light Brown fine to coarse Sandy Silt, slightly porous, weakly cemented, very dense-damp								
	✕	50/5"				112	2					
15	✕	50/5"		Red Brown fine to medium Sandy Silt, little Clay, trace coarse Sand, weakly cemented, very dense-damp								
	✕	50/5"					3					
20	✕	50/5"		Red Brown fine to medium Sandy Silt, little Clay, trace coarse Sand, weakly cemented, very dense-damp								
	✕	50/5"					3					
25	✕	50/5"		Red Brown fine to medium Sandy Silt, little Clay, trace coarse Sand, weakly cemented, very dense-damp								
	✕	50/5"					3					
30	✕	50/5"		Gray Brown fine to medium Sandy Clay, some Silt, trace Calcareous nodules/veining, weakly cemented, hard-damp								
	✕	50/5"					4					
Boring Terminated at 30'												

TBL\_22G153-1.GPJ\_SOCALGEO.GDT\_7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 6 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
15		15			ALLUVIUM: Brown fine to medium Sandy Silt, trace coarse Sand, trace fine Root Fibers, medium dense-dry		2					
5		50/5"	4.5		ALLUVIUM: Gray Brown fine to medium Sandy Clay, weakly cemented, hard-damp		5					
		50/5"			Brown Silty fine to medium Sand, trace coarse Sand, trace fine root fibers, very dense-damp		5					
10		84/11"			Brown fine to medium Sandy Silt, trace coarse Sand, very dense-dry		2					
Boring Terminated at 10'												

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 4/1/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 8 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		18		ALLUVIUM: Brown fine to coarse Sandy Silt, trace fine Gravel, trace fine root fibers, medium dense-dry		2						
		44	4.5	OLDER ALLUVIUM: Light Gray Brown fine to coarse Sandy Clay, weakly cemented, trace Calcareous veins, hard-damp		5						
5				Red Brown fine to medium Sandy Silt, little coarse Sand, trace fine root fibers, very dense-damp		4						
		67/11"		Light Gray Brown fine to coarse Sandy Clay, slightly porous, weakly cemented, hard-damp		3						
		60	4.0									
10				Boring Terminated at 10'								

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 6 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
	X	8		[Symbol]	ALLUVIUM: Brown fine to medium Sandy Silt, trace coarse Sand, trace fine Root Fibers, loose-dry		1					
5	X	70/9"	3.5	[Symbol]	OLDER ALLUVIUM: Light Red Brown fine to medium Sandy Clay, little Silt, trace coarse Sand, cemented, hard-damp		4					
	X	61/11"	3.0	[Symbol]			6					
	X	72/9"		[Symbol]	Red Brown fine to medium Sandy Silt, trace Clay, little coarse Sand, weakly cemented, very dense-damp		4					
10					Boring Terminated at 10'							

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 7 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
	X	5			ALLUVIUM: Light Red Brown fine to medium Sandy Silt, trace coarse Sand, loose-damp		2					
	X	77/11"			OLDER ALLUVIUM: Light Red Brown fine Sandy Silt, trace medium Sand, very dense-dry to damp		2					
5	X	77/6"			@ 6', weakly cemented		3					
	X	50/5"			Brown fine to coarse Sandy Silt, weakly cemented, very dense-damp		5					
10					Boring Terminated at 10'							

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/29/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 7 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)		GRAPHIC LOG	DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	
SURFACE ELEVATION: --- MSL											
		8		[Symbol]	ALLUVIUM: Brown fine to coarse Sandy Silt, loose-dry		2				
		35		[Symbol]	OLDER ALLUVIUM: Red Brown fine to coarse Sandy Silt, some Clay, weakly cemented, dense-damp		4				
5		36		[Symbol]	Red Brown fine to coarse Sandy Silt, trace Clay, dense-dry		2				
		75/11"		[Symbol]	Light Brown fine to medium Sandy Silt, trace coarse Sand, little Calcareous nodules, weakly cemented, very dense-damp		4				
10					Boring Terminated at 10'						

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 2.9 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)		GRAPHIC LOG	DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	
SURFACE ELEVATION: --- MSL											
				<u>ALLUVIUM</u> : Light Red Brown Silty fine to coarse Sand, loose-dry		2					
5	X	4		X							@ 3 1/2', No Sample Recovery
		16		X	X	2					
		50/5"		X	X	8					
10				X	X						
Boring Terminated at 10'											

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/31/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 6 feet
LOCATION: Apple Valley, California	LOGGED BY: Michelle Esparza	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
	X	13		[Dotted Pattern]	<u>ALLUVIUM</u> : Brown Silty fine to medium Sand, little coarse Sand, medium dense-dry		1					
5	X	50/5"	4.5	[Diagonal Pattern]	<u>ALLUVIUM</u> : Red Brown fine to medium Sandy Clay, little Silt, weakly cemented, hard-damp		6					
	X	59	4.5	[Diagonal Pattern]			5					
	X	50/5"	4.5	[Diagonal Pattern]			5					
10					Boring Terminated at 10'							

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22



JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 7 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
		12		ALLUVIUM: Light Brown fine to coarse Sandy Silt, trace fine Root Fibers, medium dense-dry		2						
		12		Red Brown Silty fine to coarse Sand, medium dense-dry		1						
5		62		OLDER ALLUVIUM: Orange fine to medium Sandy Silt, little coarse Sand, very dense-damp		5						
		66/10"	4.5	Brown fine to medium Sandy Clay, trace coarse Sand, little Silt, hard-damp		6						
10				Boring Terminated at 10'								

TBL 22G153-1.GPJ\_SOCALGEO.GDT 7/12/22




JOB NO.: 22G153-1	DRILLING DATE: 3/30/22	WATER DEPTH: Dry
PROJECT: Apple Valley Assemblage	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: 5 feet
LOCATION: Apple Valley, California	LOGGED BY: Joey Hernandez	READING TAKEN: At Completion

FIELD RESULTS				DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)		GRAPHIC LOG	DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	
SURFACE ELEVATION: --- MSL											
		25					2				
		59					3				
5											
		56	3.5				5				
		57					4				
10											
Boring Terminated at 10'											

TBL\_22G153-1.GPJ\_SOCALGEO.GDT 7/12/22

# A P P E N D I X C

### Consolidation/Collapse Test Results



Classification: Light Brown fine to coarse Sandy Silt


Boring Number:	B-5	Initial Moisture Content (%)	1
Sample Number:	---	Final Moisture Content (%)	12
Depth (ft)	3 to 4	Initial Dry Density (pcf)	111.7
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	127.5
Specimen Thickness (in)	1.0	Percent Collapse (%)	5.05

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 1**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Orange Brown Silty fine to coarse Sand


Boring Number:	B-5	Initial Moisture Content (%)	1
Sample Number:	---	Final Moisture Content (%)	13
Depth (ft)	5 to 6	Initial Dry Density (pcf)	107.9
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	115.9
Specimen Thickness (in)	1.0	Percent Collapse (%)	2.32

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 2**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Light Brown fine to medium Sandy Clay, trace coarse Sand


Boring Number:	B-5	Initial Moisture Content (%)	3
Sample Number:	---	Final Moisture Content (%)	12
Depth (ft)	7 to 8	Initial Dry Density (pcf)	112.0
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	119.4
Specimen Thickness (in)	1.0	Percent Collapse (%)	0.59

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 3**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Red Brown to Brown fine Sandy Clay, little Silt, trace medium Sand


Boring Number:	B-6	Initial Moisture Content (%)	5
Sample Number:	---	Final Moisture Content (%)	14
Depth (ft)	5 to 6	Initial Dry Density (pcf)	106.6
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	118.8
Specimen Thickness (in)	1.0	Percent Collapse (%)	1.72

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 4**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Light Red Brown fine to medium Sandy Silt, trace coarse Sand


Boring Number:	B-6	Initial Moisture Content (%)	5
Sample Number:	---	Final Moisture Content (%)	15
Depth (ft)	7 to 8	Initial Dry Density (pcf)	100.9
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	115.5
Specimen Thickness (in)	1.0	Percent Collapse (%)	1.88

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 5**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Light Red Brown fine to medium Sandy Silt, trace coarse Sand


Boring Number:	B-6	Initial Moisture Content (%)	3
Sample Number:	---	Final Moisture Content (%)	13
Depth (ft)	9 to 10	Initial Dry Density (pcf)	94.9
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	105.5
Specimen Thickness (in)	1.0	Percent Collapse (%)	0.88

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 6**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Light Red Brown fine to coarse Sand, trace Silt


Boring Number:	B-14	Initial Moisture Content (%)	2
Sample Number:	---	Final Moisture Content (%)	14
Depth (ft)	3 to 4	Initial Dry Density (pcf)	106.6
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	115.6
Specimen Thickness (in)	1.0	Percent Collapse (%)	4.28

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 7**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Orange Brown fine to coarse Sandy Silt, some Clay


Boring Number:	B-14	Initial Moisture Content (%)	4
Sample Number:	---	Final Moisture Content (%)	15
Depth (ft)	9 to 10	Initial Dry Density (pcf)	96.6
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	106.4
Specimen Thickness (in)	1.0	Percent Collapse (%)	1.36

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 8**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Light Red Brown fine to coarse Sandy Silt, little to some Clay


Boring Number:	B-19	Initial Moisture Content (%)	2
Sample Number:	---	Final Moisture Content (%)	11
Depth (ft)	3 to 4	Initial Dry Density (pcf)	112.4
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	129.3
Specimen Thickness (in)	1.0	Percent Collapse (%)	4.43

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 9**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Light Red Brown fine to coarse Sandy Silt, little to some Clay


Boring Number:	B-19	Initial Moisture Content (%)	2
Sample Number:	---	Final Moisture Content (%)	11
Depth (ft)	5 to 6	Initial Dry Density (pcf)	112.5
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	118.8
Specimen Thickness (in)	1.0	Percent Collapse (%)	0.24

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 10**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Light Red Brown fine to coarse Sandy Silt, trace fine Gravel


Boring Number:	B-19	Initial Moisture Content (%)	3
Sample Number:	---	Final Moisture Content (%)	14
Depth (ft)	9 to 10	Initial Dry Density (pcf)	104.3
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	116.0
Specimen Thickness (in)	1.0	Percent Collapse (%)	1.51

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 11**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Brown fine to medium Sandy Silt


Boring Number:	B-27	Initial Moisture Content (%)	2
Sample Number:	---	Final Moisture Content (%)	11
Depth (ft)	3 to 4	Initial Dry Density (pcf)	116.9
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	132.7
Specimen Thickness (in)	1.0	Percent Collapse (%)	4.26

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 12**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Red Brown fine to medium Sandy Clay, some Silt


Boring Number:	B-27	Initial Moisture Content (%)	3
Sample Number:	---	Final Moisture Content (%)	14
Depth (ft)	5 to 6	Initial Dry Density (pcf)	112.7
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	120.2
Specimen Thickness (in)	1.0	Percent Collapse (%)	0.85

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 13**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Red Brown fine to medium Sandy Clay, some Silt


Boring Number:	B-27	Initial Moisture Content (%)	3
Sample Number:	---	Final Moisture Content (%)	14
Depth (ft)	7 to 8	Initial Dry Density (pcf)	109.0
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	113.4
Specimen Thickness (in)	1.0	Percent Collapse (%)	0.31

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 14**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Brown Silty fine to medium Sand


Boring Number:	B-28	Initial Moisture Content (%)	2
Sample Number:	---	Final Moisture Content (%)	12
Depth (ft)	3 to 4	Initial Dry Density (pcf)	114.6
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	126.8
Specimen Thickness (in)	1.0	Percent Collapse (%)	4.21

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 15**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Brown fine to medium Sandy Silt, little coarse Sand


Boring Number:	B-28	Initial Moisture Content (%)	6
Sample Number:	---	Final Moisture Content (%)	12
Depth (ft)	7 to 8	Initial Dry Density (pcf)	117.5
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	128.8
Specimen Thickness (in)	1.0	Percent Collapse (%)	1.71

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 16**



**SOUTHERN  
 CALIFORNIA  
 GEOTECHNICAL**  
*A California Corporation*

### Consolidation/Collapse Test Results



Classification: Brown fine to medium Sandy Silt, little coarse Sand


Boring Number:	B-28	Initial Moisture Content (%)	2
Sample Number:	---	Final Moisture Content (%)	12
Depth (ft)	9 to 10	Initial Dry Density (pcf)	113.3
Specimen Diameter (in)	2.4	Final Dry Density (pcf)	120.6
Specimen Thickness (in)	1.0	Percent Collapse (%)	1.61

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C- 17**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*

### Moisture/Density Relationship ASTM D-1557




Soil ID Number	B-18 @ 0 to 5'
Optimum Moisture (%)	6
Maximum Dry Density (pcf)	136
Soil Classification	Red Brown fine to coarse Sandy Silt

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C-18**



### Moisture/Density Relationship ASTM D-1557




Soil ID Number	B-27 @ 0 to 5'
Optimum Moisture (%)	6.5
Maximum Dry Density (pcf)	136
Soil Classification	Brown fine to medium Sandy Silt

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C-19**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*

### Moisture/Density Relationship ASTM D-1557



Soil ID Number	B-32 @ 0 to 5'
Optimum Moisture (%)	6.5
Maximum Dry Density (pcf)	136.5
Soil Classification	Light Red Brown Silty fine to coarse Sand to fine to coarse Sandy Silt

Proposed Apple Valley Assemblage  
 Apple Valley, California  
 Project No. 22G153-1  
**PLATE C-20**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*

# APPENDIX

## **GRADING GUIDE SPECIFICATIONS**

These grading guide specifications are intended to provide typical procedures for grading operations. They are intended to supplement the recommendations contained in the geotechnical investigation report for this project. Should the recommendations in the geotechnical investigation report conflict with the grading guide specifications, the more site specific recommendations in the geotechnical investigation report will govern.

### General

- The Earthwork Contractor is responsible for the satisfactory completion of all earthwork in accordance with the plans and geotechnical reports, and in accordance with city, county, and applicable building codes.
- The Geotechnical Engineer is the representative of the Owner/Builder for the purpose of implementing the report recommendations and guidelines. These duties are not intended to relieve the Earthwork Contractor of any responsibility to perform in a workman-like manner, nor is the Geotechnical Engineer to direct the grading equipment or personnel employed by the Contractor.
- The Earthwork Contractor is required to notify the Geotechnical Engineer of the anticipated work and schedule so that testing and inspections can be provided. If necessary, work may be stopped and redone if personnel have not been scheduled in advance.
- The Earthwork Contractor is required to have suitable and sufficient equipment on the job-site to process, moisture condition, mix and compact the amount of fill being placed to the approved compaction. In addition, suitable support equipment should be available to conform with recommendations and guidelines in this report.
- Canyon cleanouts, overexcavation areas, processed ground to receive fill, key excavations, subdrains and benches should be observed by the Geotechnical Engineer prior to placement of any fill. It is the Earthwork Contractor's responsibility to notify the Geotechnical Engineer of areas that are ready for inspection.
- Excavation, filling, and subgrade preparation should be performed in a manner and sequence that will provide drainage at all times and proper control of erosion. Precipitation, springs, and seepage water encountered shall be pumped or drained to provide a suitable working surface. The Geotechnical Engineer must be informed of springs or water seepage encountered during grading or foundation construction for possible revision to the recommended construction procedures and/or installation of subdrains.

### Site Preparation

- The Earthwork Contractor is responsible for all clearing, grubbing, stripping and site preparation for the project in accordance with the recommendations of the Geotechnical Engineer.
- If any materials or areas are encountered by the Earthwork Contractor which are suspected of having toxic or environmentally sensitive contamination, the Geotechnical Engineer and Owner/Builder should be notified immediately.

- Major vegetation should be stripped and disposed of off-site. This includes trees, brush, heavy grasses and any materials considered unsuitable by the Geotechnical Engineer.
- Underground structures such as basements, cesspools or septic disposal systems, mining shafts, tunnels, wells and pipelines should be removed under the inspection of the Geotechnical Engineer and recommendations provided by the Geotechnical Engineer and/or city, county or state agencies. If such structures are known or found, the Geotechnical Engineer should be notified as soon as possible so that recommendations can be formulated.
- Any topsoil, slopewash, colluvium, alluvium and rock materials which are considered unsuitable by the Geotechnical Engineer should be removed prior to fill placement.
- Remaining voids created during site clearing caused by removal of trees, foundations basements, irrigation facilities, etc., should be excavated and filled with compacted fill.
- Subsequent to clearing and removals, areas to receive fill should be scarified to a depth of 10 to 12 inches, moisture conditioned and compacted
- The moisture condition of the processed ground should be at or slightly above the optimum moisture content as determined by the Geotechnical Engineer. Depending upon field conditions, this may require air drying or watering together with mixing and/or discing.

#### Compacted Fills

- Soil materials imported to or excavated on the property may be utilized in the fill, provided each material has been determined to be suitable in the opinion of the Geotechnical Engineer. Unless otherwise approved by the Geotechnical Engineer, all fill materials shall be free of deleterious, organic, or frozen matter, shall contain no chemicals that may result in the material being classified as "contaminated," and shall be very low to non-expansive with a maximum expansion index (EI) of 50. The top 12 inches of the compacted fill should have a maximum particle size of 3 inches, and all underlying compacted fill material a maximum 6-inch particle size, except as noted below.
- All soils should be evaluated and tested by the Geotechnical Engineer. Materials with high expansion potential, low strength, poor gradation or containing organic materials may require removal from the site or selective placement and/or mixing to the satisfaction of the Geotechnical Engineer.
- Rock fragments or rocks less than 6 inches in their largest dimensions, or as otherwise determined by the Geotechnical Engineer, may be used in compacted fill, provided the distribution and placement is satisfactory in the opinion of the Geotechnical Engineer.
- Rock fragments or rocks greater than 12 inches should be taken off-site or placed in accordance with recommendations and in areas designated as suitable by the Geotechnical Engineer. These materials should be placed in accordance with Plate D-8 of these Grading Guide Specifications and in accordance with the following recommendations:
  - Rocks 12 inches or more in diameter should be placed in rows at least 15 feet apart, 15 feet from the edge of the fill, and 10 feet or more below subgrade. Spaces should be left between each rock fragment to provide for placement and compaction of soil around the fragments.
  - Fill materials consisting of soil meeting the minimum moisture content requirements and free of oversize material should be placed between and over the rows of rock or

concrete. Ample water and compactive effort should be applied to the fill materials as they are placed in order that all of the voids between each of the fragments are filled and compacted to the specified density.

- Subsequent rows of rocks should be placed such that they are not directly above a row placed in the previous lift of fill. A minimum 5-foot offset between rows is recommended.
- To facilitate future trenching, oversized material should not be placed within the range of foundation excavations, future utilities or other underground construction unless specifically approved by the soil engineer and the developer/owner representative.
- Fill materials approved by the Geotechnical Engineer should be placed in areas previously prepared to receive fill and in evenly placed, near horizontal layers at about 6 to 8 inches in loose thickness, or as otherwise determined by the Geotechnical Engineer for the project.
- Each layer should be moisture conditioned to optimum moisture content, or slightly above, as directed by the Geotechnical Engineer. After proper mixing and/or drying, to evenly distribute the moisture, the layers should be compacted to at least 90 percent of the maximum dry density in compliance with ASTM D-1557-78 unless otherwise indicated.
- Density and moisture content testing should be performed by the Geotechnical Engineer at random intervals and locations as determined by the Geotechnical Engineer. These tests are intended as an aid to the Earthwork Contractor, so he can evaluate his workmanship, equipment effectiveness and site conditions. The Earthwork Contractor is responsible for compaction as required by the Geotechnical Report(s) and governmental agencies.
- Fill areas unused for a period of time may require moisture conditioning, processing and recompaction prior to the start of additional filling. The Earthwork Contractor should notify the Geotechnical Engineer of his intent so that an evaluation can be made.
- Fill placed on ground sloping at a 5-to-1 inclination (horizontal-to-vertical) or steeper should be benched into bedrock or other suitable materials, as directed by the Geotechnical Engineer. Typical details of benching are illustrated on Plates D-2, D-4, and D-5.
- Cut/fill transition lots should have the cut portion overexcavated to a depth of at least 3 feet and rebuilt with fill (see Plate D-1), as determined by the Geotechnical Engineer.
- All cut lots should be inspected by the Geotechnical Engineer for fracturing and other bedrock conditions. If necessary, the pads should be overexcavated to a depth of 3 feet and rebuilt with a uniform, more cohesive soil type to impede moisture penetration.
- Cut portions of pad areas above buttresses or stabilizations should be overexcavated to a depth of 3 feet and rebuilt with uniform, more cohesive compacted fill to impede moisture penetration.
- Non-structural fill adjacent to structural fill should typically be placed in unison to provide lateral support. Backfill along walls must be placed and compacted with care to ensure that excessive unbalanced lateral pressures do not develop. The type of fill material placed adjacent to below grade walls must be properly tested and approved by the Geotechnical Engineer with consideration of the lateral earth pressure used in the design.

### Foundations

- The foundation influence zone is defined as extending one foot horizontally from the outside edge of a footing, and proceeding downward at a ½ horizontal to 1 vertical (0.5:1) inclination.
- Where overexcavation beneath a footing subgrade is necessary, it should be conducted so as to encompass the entire foundation influence zone, as described above.
- Compacted fill adjacent to exterior footings should extend at least 12 inches above foundation bearing grade. Compacted fill within the interior of structures should extend to the floor subgrade elevation.

### Fill Slopes

- The placement and compaction of fill described above applies to all fill slopes. Slope compaction should be accomplished by overfilling the slope, adequately compacting the fill in even layers, including the overfilled zone and cutting the slope back to expose the compacted core
- Slope compaction may also be achieved by backrolling the slope adequately every 2 to 4 vertical feet during the filling process as well as requiring the earth moving and compaction equipment to work close to the top of the slope. Upon completion of slope construction, the slope face should be compacted with a sheepsfoot connected to a sideboom and then grid rolled. This method of slope compaction should only be used if approved by the Geotechnical Engineer.
- Sandy soils lacking in adequate cohesion may be unstable for a finished slope condition and therefore should not be placed within 15 horizontal feet of the slope face.
- All fill slopes should be keyed into bedrock or other suitable material. Fill keys should be at least 15 feet wide and inclined at 2 percent into the slope. For slopes higher than 30 feet, the fill key width should be equal to one-half the height of the slope (see Plate D-5).
- All fill keys should be cleared of loose slough material prior to geotechnical inspection and should be approved by the Geotechnical Engineer and governmental agencies prior to filling.
- The cut portion of fill over cut slopes should be made first and inspected by the Geotechnical Engineer for possible stabilization requirements. The fill portion should be adequately keyed through all surficial soils and into bedrock or suitable material. Soils should be removed from the transition zone between the cut and fill portions (see Plate D-2).

### Cut Slopes


- All cut slopes should be inspected by the Geotechnical Engineer to determine the need for stabilization. The Earthwork Contractor should notify the Geotechnical Engineer when slope cutting is in progress at intervals of 10 vertical feet. Failure to notify may result in a delay in recommendations.
- Cut slopes exposing loose, cohesionless sands should be reported to the Geotechnical Engineer for possible stabilization recommendations.
- All stabilization excavations should be cleared of loose slough material prior to geotechnical inspection. Stakes should be provided by the Civil Engineer to verify the location and dimensions of the key. A typical stabilization fill detail is shown on Plate D-5.

- Stabilization key excavations should be provided with subdrains. Typical subdrain details are shown on Plates D-6.


#### Subdrains

- Subdrains may be required in canyons and swales where fill placement is proposed. Typical subdrain details for canyons are shown on Plate D-3. Subdrains should be installed after approval of removals and before filling, as determined by the Soils Engineer.
- Plastic pipe may be used for subdrains provided it is Schedule 40 or SDR 35 or equivalent. Pipe should be protected against breakage, typically by placement in a square-cut (backhoe) trench or as recommended by the manufacturer.
- Filter material for subdrains should conform to CALTRANS Specification 68-1.025 or as approved by the Geotechnical Engineer for the specific site conditions. Clean  $\frac{3}{4}$ -inch crushed rock may be used provided it is wrapped in an acceptable filter cloth and approved by the Geotechnical Engineer. Pipe diameters should be 6 inches for runs up to 500 feet and 8 inches for the downstream continuations of longer runs. Four-inch diameter pipe may be used in buttress and stabilization fills.


CUT LOT




CUT/FILL LOT (TRANSITION)




\*SEE TEXT OF REPORT FOR SPECIFIC RECOMMENDATION.  
ACTUAL DEPTH OF OVEREXCAVATION MAY BE GREATER.

<b>TRANSITION LOT DETAIL</b>	
<b>GRADING GUIDE SPECIFICATIONS</b>	
NOT TO SCALE	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>
DRAWN: JAS CHKD: GKM	
<b>PLATE D-1</b>	




<b>FILL ABOVE CUT SLOPE DETAIL</b>	
<b>GRADING GUIDE SPECIFICATIONS</b>	
NOT TO SCALE	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>
DRAWN: JAS CHKD: GKM	
<b>PLATE D-2</b>	




PIPE MATERIAL	DEPTH OF FILL OVER SUBDRAIN
ADS (CORRUGATED POLETHYLENE)	8
TRANSITE UNDERDRAIN	20
PVC OR ABS: SDR 35	35
SDR 21	100

**SCHEMATIC ONLY  
NOT TO SCALE**

<b>CANYON SUBDRAIN DETAIL</b>	
<b>GRADING GUIDE SPECIFICATIONS</b>	
NOT TO SCALE	
DRAWN: JAS CHKD: GKM	
<b>PLATE D-3</b>	



**SOUTHERN CALIFORNIA GEOTECHNICAL**



**FILL ABOVE NATURAL SLOPE DETAIL**  
**GRADING GUIDE SPECIFICATIONS**


NOT TO SCALE


DRAWN: JAS  
 CHKD: GKM


PLATE D-4



**SOUTHERN CALIFORNIA GEOTECHNICAL**



<b>STABILIZATION FILL DETAIL</b>	
GRADING GUIDE SPECIFICATIONS	
NOT TO SCALE	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>
DRAWN: JAS CHKD: GKM	
<b>PLATE D-5</b>	




"FILTER MATERIAL" TO MEET FOLLOWING SPECIFICATION OR APPROVED EQUIVALENT: (CONFORMS TO EMA STD. PLAN 323)

SIEVE SIZE	PERCENTAGE PASSING
1"	100
3/4"	90-100
3/8"	40-100
NO. 4	25-40
NO. 8	18-33
NO. 30	5-15
NO. 50	0-7
NO. 200	0-3

"GRAVEL" TO MEET FOLLOWING SPECIFICATION OR APPROVED EQUIVALENT:

SIEVE SIZE	MAXIMUM PERCENTAGE PASSING
1 1/2"	100
NO. 4	50
NO. 200	8
SAND EQUIVALENT = MINIMUM OF 50	

OUTLET PIPE TO BE CONNECTED TO SUBDRAIN PIPE WITH TEE OR ELBOW



DETAIL "A"

FILTER MATERIAL - MINIMUM OF FIVE CUBIC FEET PER FOOT OF PIPE. SEE ABOVE FOR FILTER MATERIAL SPECIFICATION.


ALTERNATIVE: IN LIEU OF FILTER MATERIAL FIVE CUBIC FEET OF GRAVEL PER FOOT OF PIPE MAY BE ENCASED IN FILTER FABRIC. SEE ABOVE FOR GRAVEL SPECIFICATION.

FILTER FABRIC SHALL BE MIRAFI 140 OR EQUIVALENT. FILTER FABRIC SHALL BE LAPPED A MINIMUM OF 12 INCHES ON ALL JOINTS.

MINIMUM 4-INCH DIAMETER PVC SCH 40 OR ABS CLASS SDR 35 WITH A CRUSHING STRENGTH OF AT LEAST 1,000 POUNDS, WITH A MINIMUM OF 8 UNIFORMLY SPACED PERFORATIONS PER FOOT OF PIPE INSTALLED WITH PERFORATIONS ON BOTTOM OF PIPE. PROVIDE CAP AT UPSTREAM END OF PIPE. SLOPE AT 2 PERCENT TO OUTLET PIPE.

NOTES:

- TRENCH FOR OUTLET PIPES TO BE BACKFILLED WITH ON-SITE SOIL.

SLOPE FILL SUBDRAINS	
GRADING GUIDE SPECIFICATIONS	
NOT TO SCALE	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>
DRAWN: JAS CHKD: GKM	
PLATE D-6	

MINIMUM ONE FOOT THICK LAYER OF LOW PERMEABILITY SOIL IF NOT COVERED WITH AN IMPERMEABLE SURFACE


MINIMUM ONE FOOT WIDE LAYER OF FREE DRAINING MATERIAL (LESS THAN 5% PASSING THE #200 SIEVE) OR PROPERLY INSTALLED PREFABRICATED DRAINAGE COMPOSITE (MiraDRAIN 6000 OR APPROVED EQUIVALENT).

FILTER MATERIAL - MINIMUM OF TWO CUBIC FEET PER FOOT OF PIPE. SEE BELOW FOR FILTER MATERIAL SPECIFICATION.

ALTERNATIVE: IN LIEU OF FILTER MATERIAL TWO CUBIC FEET OF GRAVEL PER FOOT OF PIPE MAY BE ENCASED IN FILTER FABRIC. SEE BELOW FOR GRAVEL SPECIFICATION.

FILTER FABRIC SHALL BE MIRAFAI 140 OR EQUIVALENT. FILTER FABRIC SHALL BE LAPPED A MINIMUM OF 6 INCHES ON ALL JOINTS.

MINIMUM 4-INCH DIAMETER PVC SCH 40 OR ABS CLASS SDR 35 WITH A CRUSHING STRENGTH OF AT LEAST 1,000 POUNDS, WITH A MINIMUM OF 8 UNIFORMLY SPACED PERFORATIONS PER FOOT OF PIPE INSTALLED WITH PERFORATIONS ON BOTTOM OF PIPE. PROVIDE CAP AT UPSTREAM END OF PIPE. SLOPE AT 2 PERCENT TO OUTLET PIPE.






"FILTER MATERIAL" TO MEET FOLLOWING SPECIFICATION OR APPROVED EQUIVALENT: (CONFORMS TO EMA STD. PLAN 323)

SIEVE SIZE	PERCENTAGE PASSING
1"	100
3/4"	90-100
3/8"	40-100
NO. 4	25-40
NO. 8	18-33
NO. 30	5-15
NO. 50	0-7
NO. 200	0-3

"GRAVEL" TO MEET FOLLOWING SPECIFICATION OR APPROVED EQUIVALENT:

SIEVE SIZE	MAXIMUM PERCENTAGE PASSING
1 1/2"	100
NO. 4	50
NO. 200	8
SAND EQUIVALENT = MINIMUM OF 50	

RETAINING WALL BACKDRAINS	
GRADING GUIDE SPECIFICATIONS	
NOT TO SCALE	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>
DRAWN: JAS CHKD: GKM	
<b>PLATE D-7</b>	



**PLACEMENT OF OVERSIZED MATERIAL  
GRADING GUIDE SPECIFICATIONS**

NOT TO SCALE

DRAWN: PM  
CHKD: GKM

PLATE D-8



**SOUTHERN  
CALIFORNIA  
GEOTECHNICAL**

# APPENDIX E



Latitude, Longitude: 34.57526359, -117.175793



<b>Date</b>	7/11/2022, 9:11:33 AM
<b>Design Code Reference Document</b>	ASCE7-16
<b>Risk Category</b>	III
<b>Site Class</b>	C - Very Dense Soil and Soft Rock

Type	Value	Description
S <sub>S</sub>	1.047	MCE <sub>R</sub> ground motion. (for 0.2 second period)
S <sub>1</sub>	0.4	MCE <sub>R</sub> ground motion. (for 1.0s period)
S <sub>MS</sub>	1.257	Site-modified spectral acceleration value
S <sub>M1</sub>	0.6	Site-modified spectral acceleration value
S <sub>DS</sub>	0.838	Numeric seismic design value at 0.2 second SA
S <sub>D1</sub>	0.4	Numeric seismic design value at 1.0 second SA

Type	Value	Description
SDC	D	Seismic design category
F <sub>a</sub>	1.2	Site amplification factor at 0.2 second
F <sub>v</sub>	1.5	Site amplification factor at 1.0 second
PGA	0.449	MCE <sub>G</sub> peak ground acceleration
F <sub>PGA</sub>	1.2	Site amplification factor at PGA
PGA <sub>M</sub>	0.539	Site modified peak ground acceleration
T <sub>L</sub>	12	Long-period transition period in seconds
SsRT	1.047	Probabilistic risk-targeted ground motion. (0.2 second)
SsUH	1.121	Factored uniform-hazard (2% probability of exceedance in 50 years) spectral acceleration
SsD	1.582	Factored deterministic acceleration value. (0.2 second)
S1RT	0.4	Probabilistic risk-targeted ground motion. (1.0 second)
S1UH	0.434	Factored uniform-hazard (2% probability of exceedance in 50 years) spectral acceleration.
S1D	0.6	Factored deterministic acceleration value. (1.0 second)
PGAd	0.66	Factored deterministic acceleration value. (Peak Ground Acceleration)
C <sub>RS</sub>	0.934	Mapped value of the risk coefficient at short periods
C <sub>R1</sub>	0.923	Mapped value of the risk coefficient at a period of 1 s

SOURCE: SEAOC/OSHPD Seismic Design Maps Tool  
<<https://seismicmaps.org/>>



<b>SEISMIC DESIGN PARAMETERS - 2019 CBC</b>	
PROPOSED APPLE VALLEY ASSEMBLAGE	
APPLE VALLEY, CALIFORNIA	
DRAWN: JJH CHKD: DN SCG PROJECT 22G153-1 <b>PLATE E-1</b>	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>